

COGIS - Field Inspection Report

API Number: 05-121-10711	Name: CHRISTIANSEN #B-5
Location: NENW 27 3S 50W	Lat: 39.76917 Long: -102.96724
Operator #:	Operator Name: CORAL PRODUCTION CORP
Inspection Date: 4/29/2011	Inspector: JOHN AXELSON

Inspection was: **Unsatisfactory**

Insp. Type: ES	Insp. Stat: PR	Reclamation (Pass, Interim or Fail):	P&A (Pass/Fail):
Brhd. Pressure:	Inj. Pressure:	T-C Ann. Pressure:	UIC Violation Type:
Violation: Y	NOAV Sent: Y	Date Corrective Action Due: 7/31/2011	Date Remedied:

Pit Inspection

Pit Type: **PW** Oil on Pit: **N** Freeboard:Number of Pits: **1** Number covered or lined: **0** Number uncovered or unlined: **0**

Comments: **PRODUCED WATER PIT APPROX 130' X 400' WITH SIPHON PIPE AT SOUTH END FLOWS TO BURIED STEEL TANK WITH 3" BLACK POLY PIPE FLOWING WATER TO LAKE SOUTH OF PIT.**

Pit Type: **SS** Oil on Pit: Freeboard:Number of Pits: **6** Number covered or lined: **6** Number uncovered or unlined:

Comments: **4: SKIM PITS IN USE; 2: SKIM PITS NO LONGER IN USE - 1-PIT IS FILLED WITH SAND, 1-PIT IS DRY. ALL PITS ARE UNLINED AND SURROUNDED BY OIL SATURATED SOILS.**

Tank Battery Equipment Steel Tanks: **1**

Field Inspection Comments and Observations

Insp. Comment	Inspection/Violation Comments
ACTION	SUBMIT A FORM 19 TO DOCUMENT THE INTENTIONAL DUMPING OF TANK BOTTOMS ON THE LEASE ROADS. IMMEDIATELY REMOVE ALL IMPACTED MATERIAL ON THE LEASE ROADS RESULTING FROM THE DUMPING OF THE TANK BOTTOMS AND PROPERLY DISPOSE IN ACCORDANCE WITH COGCC RULE 907.E. PROVIDE DOCUMENTATION OF VOLUME OF MATERIAL REMOVED AND DISPOSAL INFORMATION. COLLECT A SUFFICIENT NUMBER OF CONFIRMATION SOIL SAMPLES FROM REMOVAL AREAS TO VERIFY THAT ALL REMAINING MATERIAL MEETS TABLE 910-1 STANDARDS. SUBMIT DISPOSAL DOCUMENTATION AND CONFIRMATION SAMPLE RESULTS ON A FORM 27. REMOVE AND PROPERLY DISPOSE IN ACCORDANCE WITH RULE 907.E. ALL SITE WIDE OILY SOILS. DISPOSAL DOCUMENTATION AND SAMPLE RESULTS CAN BE INCLUDED ON SAME FORM 27. PROVIDE WELL & BATTERY SIGNS WITH ALL INFORMATION REQUIRED IN ACCORDANCE WITH RULE 210.B. PROPERLY LABEL TANKS IN ACCORDANCE WITH RULE 210.D. REMOVE ALL JUNK, TRASH, DEBRIS FROM LOCATION AND PROPERLY DISPOSE OR RECYCLE IN ACCORDANCE WITH RULE 603.J. MAINTAIN ALL EQUIPMENT TO PREVENT LEAKS AND SPILLS IN ACCORDANCE WITH RULE 604.D. SUBMIT DOCUMENTATION VERIFYING PERMITTED DISCHARGE OF PRODUCED WATER FROM PIT. SUBMIT SEPARATE FORM 27 FOR PROPER CLOSURE OF UNLINED SKIM PITS IN ACCORDANCE WITH RULE 905. ONCE

	CLOSURE REQUIREMENTS ARE MET, SKIM PITS CAN BE PROPERLY LINED OR REPLACED WITH SKIM VESSELS. ALL OIL SATURATED SOIL SURROUNDING SKIM PITS WILL REQUIRE APPROPRIATE DISPOSAL IN ACCORDANCE WITH RULE 907.E. IF DISCHARGE FROM WATER PIT IS NOT PERMITTED, IMMEDIATELY STOP DISCHARGE. NOTIFY SURFACE OWNER OF INTENTIONAL DUMPING ON LEASE ROADS AND PLANNED REMEDIATION.
FENCECOMMENT	TANK BATTERY FENCED.
FIREWALL	BERMS IN BAD CONDITION. SOME FRESH DIRT HAS RECENTLY BEEN SPREAD OVER BERMS PARTIALLY COVERING OIL SATURATED SOIL.
GENHOUSE	JUNK AND TRASH OBSERVED SITE WIDE INCLUDING PIPE, METAL, 5-GAL CONTAINERS, 55-GAL DRUMS, MISC. DEBRIS. WEEDS HAVEN'T BEEN CONTROLLED. LEAKING DRIPPING EQUIPMENT. TANKS NOT PROPERLY LABELLED. BURIED STEEL WATER TANK HAS UNCOVERED OPENINGS. NO INDICATION OF ROUTINE HOUSEKEEPING/MAINTENANCE. OLD PUMPING UNIT STORED ON SITE.
MISC	CONTACTED SAM SPEARS PUMPER FOR CORAL PRODUCTION. HE ESTIMATED TANK BOTTOMS HAD BEEN DUMPED APPROXIMATELY TWO WEEKS AGO AT THE DIRECTION OF CORAL PRODUCTION. HE COULD NOT VERIFY VOLUME, BUT THOUGHT THERE WERE 20-30 BBLs OF FLUIDS AND SAND. CONTRACTOR ON LOCATION DRAGGING OIL INTO THE LEASE ROADS AT TIME OF INSPECTION SAID HE WAS LANDFARMING MATERIAL. SAM SPEARS THOUGHT THAT DISCHARGE FROM WATER PIT WAS PERMITTED.
SPILCOM	DURING CLEANOUT OF TANK BOTTOMS FROM TANKS ON LOCATION, OIL AND OILY MATERIAL WAS SPREAD ON TURN-AROUND AT BATTERY AND ALONG LEASE ROADS. FROM TURN-AROUND, OIL WAS SPREAD ON LEASE ROAD APPROXIMATELY 715- FEET NORTH TO INTERSECTION. FROM INTERSECTION WEST APPROXIMATELY 600- FEET TO CHRISTIANSON 1 PUMPING UNIT AND FROM INTERSECTION EAST APPROXIMATELY 650- FEET TO CHRISTIANSON B3 PUMPING UNIT. IN ADDITION, OIL WAS INTENTIONALL SPREAD ON LEASE ROAD TO NORTH FROM A POINT STARTING APPROXIMATELY 1100- FEET DUE EAST OF COUNTY ROAD RR ALONG LEASE ROAD 1-MILE TO EAST AND SOUTH ENDING AT THE YOUNG 33-27350 TANK BATTERY. IN ADDITION TO INTENTIONAL DUMPING, LARGE VOLUMES OF OIL SATURATED SOIL WAS OBSERVED SITE WIDE THROUGHOUT TANK BATTERY AND WATER PIT COMPLEX.
TANKBAT	5: 300 BBL STEEL PROD TANKS; 2: 400 BBL STEEL WATER TANKS; 2- SHEDS; PROPANE TANK. SHARED BATTERY WITH THE CHRISTIANSON 1, B3, B4-WD & B-5.
WELLSIGN	SIGN AT BATTERY HAS NO OPERATOR INFO AND WRONG COUNTY.