



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 338220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7299

6-634

OUR INVOICE

REC'D EUSD 198355

AUG 18 2010

(P.O. #. 660229)

Date 8-12-10	Well Owner FDC	Well No. 44-18	Lease GUTTERSEN
Country WELD	State COLORADO	Field	
Charge to ENSIGN US DRILLING	Charge Code		For Office Use Only
Address RD BOX 17805 (ENSIGN-5)			
City, State DENVER COLORADO 80217			
Pump Truck No. 1202	Code	Bulk Truck No. 1207	Code
Type of Job	Depth	Ft. 727	To
Surface 8 5/8" CSG-24#	Bottom of Surface	Ft. 717	To
Plug	Plug Landed @ 679	Ft. Time On 0230	
Production	Pipe Landed @ 717	Ft. Time Off 0430	

Reference No.	Description	Qty.	Meas.	Unit Price		
	Pump Truck Charge					
	Cement Neat ✓	510	SKS			
	Poz. Mix					
	Calcium Chloride	3%				
	Gel % Flo-Cele 1/4 #Per Sack					
	Handling Charge					
	Hauling Charge					
	Additional Cement					
8 5/8"	CENTRALIZERS	4		70.00		
	CEMENT BASKET	1				
	GUIDE SHOE	1				
	BAFFLE PLATE	1				
	BOX THREADLOCK	1				
MIX RATE 4 BPM		SLURRY VOL 1.18 FT ³ /SK - WATER		TEMP 80		
DISP RATE 5 BPM		SLURRY WT 15.2 PPG				
PLUG LANDED @ 700 PSI		TOTAL SLURRY VOL 107		BBL CEMENT		
Remarks:	YREKLEH W/ 20 BBL H2O	Tax Reference Code		Sub Total		
DISPLACE W/ 43 BBL H2O		State CO 2-9 *		Tax		
CIRCULATE 6 BBL CEMENT		Disc.		Total		
Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other
1202		Pump Truck		76		
1207		Bulk Truck		76		

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review.

Delivered By Mr. JOSH KERRY

Received By [Signature]
Customer or His