

FORM
2
Rev
12/05

State of Colorado
Oil and Gas Conservation Commission
1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400142695

Plugging Bond Surety

20010124

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☒ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐

Refiling ☐
Sidetrack ☐

3. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP 4. COGCC Operator Number: 47120
5. Address: P O BOX 173779
City: DENVER State: CO Zip: 80217-3779
6. Contact Name: REBECCA HEIM Phone: (720)929-6361 Fax: (720)929-7361
Email: rebecca.heim@anadarko.com
7. Well Name: THOMASON Well Number: 23-16
8. Unit Name (if appl): _____ Unit Number: _____
9. Proposed Total Measured Depth: 7451

WELL LOCATION INFORMATION

10. QtrQtr: NESW Sec: 16 Twp: 2N Rng: 65W Meridian: 6
Latitude: 40.136692 Longitude: -104.671175

Footage at Surface: 1904 feet FNL/FSL 2023 feet FEL/FWL FWL

11. Field Name: WATTENBERG Field Number: 90750
12. Ground Elevation: 4885 13. County: WELD

14. GPS Data:

Date of Measurement: 10/27/2010 PDOP Reading: 2.4 Instrument Operator's Name: BEN MILIUS

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 1270 FSL 2580 FWL FWL Bottom Hole: FNL/FSL 1270 FSL 2580 FWL FWL
Sec: 16 Twp: 2N Rng: 65W Sec: 16 Twp: 2N Rng: 65W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 596 ft

18. Distance to nearest property line: 613 ft 19. Distance to nearest well permitted/completed in the same formation: 931 ft

20. **LEASE, SPACING AND POOLING INFORMATION**

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA-CODELL	NB-CD	407	160	GWA

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☒ No

23b. If 23 is No ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
PLEASE SEE ATTACHED OGL.

25. Distance to Nearest Mineral Lease Line: _____ 45 ft 26. Total Acres in Lease: _____ 318

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	8+5/8	24	0	900	630	900	0
1ST	7+7/8	4+1/2	11.6	0	7,451	200	7,451	0

32. BOP Equipment Type: ☒ Annular Preventer ☐ Double Ram ☒ Rotating Head ☐ None

33. Comments NO CONDUCTOR CASING WILL BE USED. UNIT CONFIGURATION: NB-CD E/2SW; W/2SE/4

34. Location ID: _____ 329312

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: REBECCA HEIM

Title: REGULATORY ANALYST II Date: 3/23/2011 Email: DJREGULATORY@ANADARK

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 5/5/2011

API NUMBER

05 123 33479 00

Permit Number: _____ Expiration Date: 5/4/2013

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- 1) Provide 24 hour notice of MIRU to Jim Precup at 303-469-1902 or e-mail at james.precup@state.co.us
- 2) Provide cement coverage from TD to a minimum of 200' above Niobrara and from 200' below Sussex to 200' above Sussex. Verify coverage with cement bond log.
- 3) Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

Attachment Check List

Att Doc Num	Name
2111528	SURFACE CASING CHECK
400142695	FORM 2 SUBMITTED
400142736	DEVIATED DRILLING PLAN
400142737	30 DAY NOTICE LETTER
400142738	WELL LOCATION PLAT
400142739	PROPOSED SPACING UNIT
400142740	SURFACE AGRMT/SURETY
400142741	TOPO MAP
400142742	OIL & GAS LEASE

Total Attach: 9 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)