



Document Number:

400142646

Plugging Bond Surety

20010124

**APPLICATION FOR PERMIT TO:**

1. ☒ **Drill,** ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

**2. TYPE OF WELL**

OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_  
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☐

Refiling ☐  
Sidetrack ☐

3. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP 4. COGCC Operator Number: 47120

5. Address: P O BOX 173779  
City: DENVER State: CO Zip: 80217-3779

6. Contact Name: REBECCA HEIM Phone: (720)929-6361 Fax: (720)929-7361  
Email: rebecca.heim@anadarko.com

7. Well Name: THOMASON Well Number: 6-16

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 7516

**WELL LOCATION INFORMATION**

10. QtrQtr: NESW Sec: 16 Twp: 2N Rng: 65W Meridian: 6  
Latitude: 40.136824 Longitude: -104.671175

Footage at Surface: 1952 feet FNL/FSL 2023 feet FEL/FWL FWL

11. Field Name: WATTENBERG Field Number: 90750

12. Ground Elevation: 4885 13. County: WELD

**14. GPS Data:**

Date of Measurement: 10/27/2010 PDOP Reading: 2.4 Instrument Operator's Name: BEN MILIUS

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 2130 FNL 2130 FWL 2130 FNL 2130 FWL 2130  
Sec: 16 Twp: 2N Rng: 65W Sec: 16 Twp: 2N Rng: 65W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 596 ft

18. Distance to nearest property line: 613 ft 19. Distance to nearest well permitted/completed in the same formation: 679 ft

**20. LEASE, SPACING AND POOLING INFORMATION**

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA-CODELL	NB-CD	407	80	E/2NW/4
SUSSEX	SUSX		80	E/2NW/4

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: \_\_\_\_\_

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☒ No

23b. If 23 is No ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
PLEASE SEE ATTACHED OGL.

25. Distance to Nearest Mineral Lease Line: \_\_\_\_\_ 496 ft 26. Total Acres in Lease: \_\_\_\_\_ 318

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: \_\_\_\_\_

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	8+5/8	24	0	900	630	900	0
1ST	7+7/8	4+1/2	11.6	0	7,516	200	7,516	0

32. BOP Equipment Type: ☒ Annular Preventer ☐ Double Ram ☒ Rotating Head ☐ None

33. Comments NO CONDUCTOR CASING WILL BE USED.

34. Location ID: \_\_\_\_\_ 329312

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: REBECCA HEIM

Title: REGULATORY ANALYST II Date: 3/23/2011 Email: DJREGULATORY@ANADARK

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 5/5/2011

#### API NUMBER

05 123 33480 00

Permit Number: \_\_\_\_\_ Expiration Date: 5/4/2013

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- 1) Provide 24 hour notice of MIRU to Jim Precup at 303-469-1902 or e-mail at james.precup@state.co.us
- 2) Provide cement coverage from TD to a minimum of 200' above Niobrara and from 200' below Sussex to 200' above Sussex. Verify coverage with cement bond log.
- 3) Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

### Attachment Check List

Att Doc Num	Name
2111528	SURFACE CASING CHECK
400142646	FORM 2 SUBMITTED
400142650	30 DAY NOTICE LETTER
400142651	PLAT
400142652	SURFACE AGRMT/SURETY
400142653	TOPO MAP
400142654	OIL & GAS LEASE
400142693	DEVIATED DRILLING PLAN

Total Attach: 8 Files

### General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

### BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)