



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

198963

Date <u>2/13/11</u>	Well Owner <u>KERR McGEE</u>	Well No. <u>23-18</u>	Lease <u>DENVER</u>
County <u>Weld</u>	State <u>Colorado</u>	Field	
Charge to <u>KERR McGEE Oil & Gas ONSHORE, LP</u>			Charge Code
Address <u>1999 Broadway, Suite 3700 (Patterson #189)</u>			For Office Use Only
City, State <u>Denver, Colorado 80202</u>			
Pump Truck No. <u>1208</u>	Code	Bulk Truck No. <u>1214/1217</u>	Code
Type of Job	Depth	Ft. <u>1002</u>	To
<u>Surface</u> <u>8 5/8" CSG-24"</u>	Bottom of Surface	Ft. <u>992</u>	To
Plug	Plug Landed @ <u>948</u>	Ft.	Time On <u>0820</u>
Production	Pipe Landed @ <u>992</u>	Ft.	Time Off <u>Plug Down 1015</u>

Reference No.	Description	Qty.	Meas.	Unit Price	Amount
	Pump Truck Charge				
	Cement Neat <u>Type III</u>	<u>630</u>	<u>SKS</u>		
	Poz. Mix				
	Calcium Chloride	<u>2.5%</u>			
	Gel % Flo-Cele <u>1/4</u> #Per Sack			MIKE LINGREEN	
	Handling Charge			User ID ZMDL6	
	Hauling Charge				
	Additional Cement			WBSN/ICC <u>204.5925 DRL</u>	
	Mixing Rate - 4 BPM	Pre-Flush	0927-	0930 Acct	<u>20012090</u>
	Disp Rate - 5 BPM	Mixing	0933-	1000	
	Slurry Vol - 1.32 cu FT/SK	Change Valves	1000-	1003	
	Slurry WT 14.8-15.0 PPG	Disp.	1003-	1015	
	Water/Cement - 6.25 Gal/SK				
	Water Temp 78°F				
	Total Slurry Vol 148 BBLS Cement				
	Landed Plug @ 400 PSI / Final Lift @ 200 PSI				

Remarks: <u>Pre-Flush w/ 30 BBLS H²O</u>	Tax Reference Code	Sub Total
<u>Displace w/ 60 BBLS H²O</u>	State <u>CO 2.9</u> %	Tax
<u>Circulate 6 BBLS Cement</u>	Disc.	Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<u>1208</u>		Pump Truck		<u>60</u>			
<u>1214/1217</u>		Bulk Truck		<u>60/60</u>			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Justin, Dallas, James & Justin

Received By

Greg Horvath
Customer or His Agent