

FORM  
2  
Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

APPLICATION FOR PERMIT TO:

1.  Drill,  Deepen,  Re-enter,  Recomplete and Operate

2. TYPE OF WELL

OIL  GAS  COALBED  OTHER \_\_\_\_\_  
SINGLE ZONE  MULTIPLE ZONE  COMMINGLE ZONE

Refilling   
Sidetrack

Document Number:  
400159623  
Plugging Bond Surety  
20030058

3. Name of Operator: EOG RESOURCES INC 4. COGCC Operator Number: 27742

5. Address: 600 17TH ST STE 1100N  
City: DENVER State: CO Zip: 80202

6. Contact Name: Nanette Lupcho Phone: (435)781-9157 Fax: (435)789-7633  
Email: Nanette\_Lupcho@eogresources.com

7. Well Name: Dutch Lake Well Number: 19-27H

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 10696

WELL LOCATION INFORMATION

10. QtrQtr: SESE Sec: 27 Twp: 6N Rng: 62W Meridian: 6  
Latitude: 40.452589 Longitude: -104.301278

Footage at Surface: 501 feet FSL 501 feet FWL

11. Field Name: Wildcat Field Number: 99999

12. Ground Elevation: 4688 13. County: WELD

14. GPS Data:

Date of Measurement: 01/26/2011 PDOP Reading: 1.4 Instrument Operator's Name: Robert Kay

15. If well is  Directional  Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL  
890 FSL 726 FEL 600 FNL 2639 FEL  
Sec: 27 Twp: 6N Rng: 62W Sec: 27 Twp: 6N Rng: 62W

16. Is location in a high density area? (Rule 603b)?  Yes  No

17. Distance to the nearest building, public road, above ground utility or railroad: 2276 ft

18. Distance to nearest property line: 501 ft 19. Distance to nearest well permitted/completed in the same formation: 1350 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Niobrara	NBRR	535-4	640	All

21. Mineral Ownership:  Fee  State  Federal  Indian Lease #: \_\_\_\_\_

22. Surface Ownership:  Fee  State  Federal  Indian

23. Is the Surface Owner also the Mineral Owner?  Yes  No Surface Surety ID#: 20090114

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease?  Yes  No

23b. If 23 is No  Surface Owners Agreement Attached or  \$25,000 Blanket Surface Bon  \$2,000 Surface Bond  \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
Please see attached lease description.

25. Distance to Nearest Mineral Lease Line: 600 ft 26. Total Acres in Lease: 4360

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated?  Yes  No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling?  Yes  No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling?  Yes  No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)?  Yes  No

31. Mud disposal:  Offsite  Onsite **If 28, 29, or 30 are "Yes" a pit permit may be required.**

Method:  Land Farming  Land Spreading  Disposal Facility Other: \_\_\_\_\_

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	20	16	42	0	60	50	60	0
SURF	13+1/2	9+5/8	36	0	800	420	800	0
1ST	8+3/4	7	23	0	6,598	700	6,598	0
1ST LINER	6	4+1/2	11.6	5848	10,696	300	10,696	5,848

32. BOP Equipment Type:  Annular Preventer  Double Ram  Rotating Head  None

33. Comments Distance to nearest well was measured from the Dutch Lake 19-27H SHL to the SHL of the pending EOG Dutch Lake 23-35H well.

34. Location ID: \_\_\_\_\_

35. Is this application in a Comprehensive Drilling Plan ?  Yes  No

36. Is this application part of submitted Oil and Gas Location Assessment ?  Yes  No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Nanette Lupcho

Title: Regulatory Assistant Date: \_\_\_\_\_ Email: Nanette\_Lupcho@eogresource

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

<b>API NUMBER</b>	Permit Number: _____	Expiration Date: _____
05	<b>CONDITIONS OF APPROVAL, IF ANY:</b>	

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

--

**Attachment Check List**

Att Doc Num	Name
400159641	DRILLING PLAN
400159642	DEVIATED DRILLING PLAN
400159643	TOPO MAP
400159646	PLAT
400159647	LEGAL/LEASE DESCRIPTION

Total Attach: 5 Files

**General Comments**

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

**BMP**

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)