



COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

Document Number:

400164337

1. OGCC Operator Number: 10203

4. Contact Name: Madeleine Lariviere

2. Name of Operator: BLACK RAVEN ENERGY INC

Phone: (303) 308-1330

3. Address: 1331 17TH STREET - #350

Fax: (303) 308-1590

City: DENVER State: CO Zip: 80202

5. API Number 05-095-06229-00

6. County: PHILLIPS

7. Well Name: WALTERS

Well Number: 943-32-34

8. Location: QtrQtr: SWSE Section: 32 Township: 9N Range: 43W Meridian: 6

9. Field Name: AMHERST Field Code: 2480

Completed Interval


FORMATION: NIOBRARA

Status: PRODUCING

Treatment Date: 02/12/2011 Date of First Production this formation: 02/26/2011

Perforations	Top:	2406	Bottom:	2422	No. Holes:	64	Hole size:	6 + 1/4
--------------	------	------	---------	------	------------	----	------------	---------

Provide a brief summary of the formation treatment:

Open Hole: 

Frac Niobrara with Maverick Stimulation using 28 # crosslinked gel 50,060 #16/30 Arizona sand and 50,120 # 12/20 Texas Gold sand for a total of 100,180 # sand. 60 tons CO2. 546 BLWTR. 5 MIN- 623 PSI 10 MIN-602 PSI. 15 MIN-593 PSI . MAX RATE 13.9 AVG RATE 9.7 MAX PSI- 1309 AVG PSI 732 isip-713 psi

This formation is commingled with another formation: ☐ Yes ☒ No

Test Information:

Date:	03/01/2011	Hours:	24	Bbls oil:	0	Mcf Gas:	139	Bbls H2O:	0
-------	------------	--------	----	-----------	---	----------	-----	-----------	---

Calculated 24 hour rate:	Bbls oil:	0	Mcf Gas:	139	Bbls H2O:	0	GOR:
--------------------------	-----------	---	----------	-----	-----------	---	------

Test Method: Flow Test	Casing PSI: 195	Tubing PSI: 0	Choke Size: 16/64
------------------------	-----------------	---------------	-------------------

Gas Disposition:	SOLD	Gas Type:	DRY	BTU Gas:	0	API Gravity Oil:	0
------------------	------	-----------	-----	----------	---	------------------	---

Tubing Size: 2 + 3/8 Tubing Setting Depth: 2391 Tbg setting date: 05/11/2011 Packer Depth:

Reason for Non-Production:

Date formation Abandoned: ☐ Squeeze: ☐ Yes ☐ No If yes, number of sacks cmt

Bridge Plug Depth: _____ Sacks cement on top: _____

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Madeleine Lariviere

Title: Office Manager Date: Email: mlariviere@blackravenenergy.com

Based on the information provided herein, this Completed Interval Report (Form 5A) complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

Attachment Check List

Att Doc Num	Name
400164345	WELLBORE DIAGRAM

Total Attach: 1 Files

General Comments

User Group	Comment	Comment Date

Total: 0 comment(s)