



# CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

## 199064

Date <u>03/10/2011</u>	Well Owner <u>KERR MCGEE</u>	Well No. <u>23-27</u>	Lease <u>WILDFLOWER</u>
County <u>WELD</u>	State <u>COLORADO</u>	Field	
Charge to <u>KERR MCGEE OIL &amp; GAS ONSHORE LP</u>	Charge Code		
Address <u>1999 BROADWAY STE 3700 (PATTERSON) #189</u>	For Office Use Only		
City, State <u>DENVER COLORADO 80202</u>			
Pump Truck No. <u>1201</u>	Code	Bulk Truck No. <u>1214/1218</u>	Code
Type of Job <u>Surface 8 5/8 CSG 24"</u>	Depth	Ft. <u>892</u>	To
Plug	Bottom of Surface	Ft. <u>881</u>	To
Production	Plug Landed @ <u>837</u>	Fl. Time On <u>2300</u>	
	Pipe Landed @ <u>881</u>	Fl. Time Off <u>PLUG DOWN 0215</u>	

Reference No.	Description	Qty.	Meas.	Unit Price	Amount	
	Pump Truck Charge <u>2040515.DRC</u>	1				
	Cement Net <u>00012090</u>	550	SKS	14.85		
	TYPE III					
	Poz. Mix					
	Calcium Chloride	25%				
	Gel % Flo-Cele <u>1/4</u> #Per Sack					
	Handling Charge <u>FUEL SURCHARGE</u>	270	MTLES	.08		
	Hauling Charge <u>MILEAGE</u>	270	MTLES	3.00		
	Additional Cement					
	MTXING RATE 4BPM	PRE-FLUSH		0131-0137		
	DISP. RATE 5BPM	MIX		0137-0201		
	SLURRY VOL 132 CUFT <sup>3</sup> /SK	CHANGE VALVES		0201-0204		
	SLURRY WT 14.8-15.0 PPG	DISPLACE		0204-0215		
	WATER/CEMENT 6.25 GAL/SK					
	WATER TEMP 50°F					
	TOTAL SLURRY VOL 129.3 BBLs CEMENT					
	LANDED PLUG @ 425 PST / FINAL LIFT @ 75 PST					
Remarks:	<u>PRE-FLUSH W/130 BBLs H<sup>2</sup>O</u>	Tax Reference Code	Sub Total			
	<u>DISPLACE W/53 BBLs H<sup>2</sup>O</u>	State <u>CO 2.9 %</u>	Tax			
	<u>CIRCULATE 5 BBLs CEMENT</u>	Disc.	Total			
Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other
<u>1201</u>		Pump Truck		90		
<u>1214/1218</u>		Bulk Truck		90/90		

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By JIM/OSCAR/STEVE/ADAM

Received By [Signature]

Customer or His Agent