

Kubeczko, Dave

From: Kubeczko, Dave
Sent: Tuesday, May 17, 2011 4:47 PM
To: Kubeczko, Dave
Subject: FW: Dakota Exploration LLC, State 6-81-24-4, NWNW Sec 24 T6N R81W, Jackson County, Form 2A (#400157400) Review

Categories: Orange Category

Scan No 2033818 CORRESPONDENCE 2A#400157400

From: Fabrianna Venaducci [<mailto:fabrianna@jameskaro.com>]
Sent: Wednesday, May 11, 2011 2:28 PM
To: Kubeczko, Dave
Cc: Duane Russell
Subject: RE: Dakota Exploration LLC, State 6-81-24-4, NWNW Sec 24 T6N R81W, Jackson County, Form 2A (#400157400) Review

Dave,

Dakota Exploration, LLC, as Operator, accepts the Conditions of Approval as set forth below.

Thank you,

fabrianna venaducci
james c karo associates
1750 lafayette street
denver, co 80218
303-279-0789

NOTE: This electronic communication may contain CONFIDENTIAL INFORMATION which also may be LEGALLY PRIVILEGED and which is intended only for the use of the addressee named above. If you are not the intended recipient of this communication, or the employee or agent responsible for delivering it to the intended recipient, you are hereby notified that any dissemination or copying of this communication may be strictly prohibited. If you have received this communication in error, please notify us immediately by replying to this communication and deleting it from your computer. Thank you. James C Karo Associates

From: Kubeczko, Dave [<mailto:Dave.Kubeczko@state.co.us>]
Sent: Tuesday, May 10, 2011 8:15 AM
To: Fabrianna Venaducci
Subject: Dakota Exploration LLC, State 6-81-24-4, NWNW Sec 24 T6N R81W, Jackson County, Form 2A (#400157400) Review

Fabrianna,

I have been reviewing the State 6-81-24-4 **Form 2A** (#400157400). COGCC would like to attach the following conditions of approval (COAs) based on the information and the data Dakota has submitted on or attached to the Form 2A prior to passing the Oil and Gas Location Assessment (OGLA) review.

1. **General:** The following conditions of approval (COAs) will apply:

COA 6 - Reserve pit must be lined or a closed loop system must be implemented during drilling.

COA 23 - Operator must ensure secondary containment for any volume of fluids contained at well site during drilling and completion operations; including, but not limited to, construction of a berm or diversion dike, diversion/collection trenches within and/or outside of berms/dikes, site grading, or other comparable measures (i.e., best management practices (BMPs) associated with stormwater management) sufficiently protective of nearby surface water. Any berm constructed at the well pad location will be stabilized, inspected at regular intervals (at least every 14 days), and maintained in good condition.

COA 25 - Flowback and stimulation fluids must be sent to tanks before the fluids can be placed into any pipeline or pit located on the well pad. The flowback and stimulation fluid tanks must be placed on the well pad in an area with additional downgradient perimeter berming. The area where flowback fluids will be stored/reused must be constructed to be sufficiently impervious to contain any spilled or released material (per Rule 604.a.(4)).

COA 58 - Berms or other containment devices shall be constructed in compliance with Rule 604.a.(4) around crude oil, condensate, and produced water storage tanks.

COA 38 - The moisture content of any drill cuttings in a cuttings pit, trench, or pile shall be as low as practicable to prevent accumulation of liquids greater than de minimis amounts. At the time of closure, the drill cuttings must also meet the applicable standards of table 910-1.

COA 39 - No portion of any pit that will be used to hold liquids shall be constructed on fill material, unless the pit and fill slope are designed and certified by a professional engineer, subject to review and approval by the director prior to construction of the pit. The construction and lining of the pit shall be supervised by a professional engineer or their agent. The entire base of the pit must be in cut.

COGCC would appreciate your concurrence with attaching these COAs (item 1) to the Form 2A permit prior to passing the OGLA review. If you have any questions, please do not hesitate to call me at (970) 309-2514 (cell), or email.

Thanks.

Dave

David A. Kubeczko, PG
Oil and Gas Location Assessment Specialist

Colorado Oil & Gas Conservation Commission
Northwest Area Office
707 Wapiti Court, Suite 204
Rifle, CO 81650
Phone: (970) 625-2497x5
FAX: (970) 625-5682
Cell: (970) 309-2514
dave.kubeczko@state.co.us



 *Please consider the environment before printing this e-mail*