



02055111

FORM

23

Rev. 5/99

State of Colorado Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 (303) 894-2100 Fax: (303) 894-2109



FOR OGCC USE ONLY

RECEIVED

MAY 09 2011

COGCC

LOSS OF WELL CONTROL REPORT

As required by Rule 327.

1. OGCC Operator Number: 100185	4. Contact Name & Phone Miracle Pfister	Report taken by:
2. Name of Operator: Encana Oil & Gas	Ph: (720)876-3761	DAVE ANDREWS
3. Address: 370 17th St Suite 1700	Fax: (720)876-6060	
City: Denver State: CO Zip: 80202		

WELL LOCATION INFORMATION

5. API Number: 05-045-20168-00	6. County: Garfield
7. Well Name: Benjamin Federal	8. Well Number: 28-13B2 (K 28 NW)
9. Unit Name (if appl.): Grass Mesa	10. Unit No: COC056608X
11. Qtr/Sec: NESW Sec 28 Twp: 6S Rng: 93W Meridian: 6	
12. Footage From Extensor Section Lines: 1628 FSL and 2425 FWL	
13. Field Name: Mamm Creek	14. Field Number: 52500

CASING INFORMATION

15. Surface Casing Size: 9 5/8 / Weight per Foot: 36 Grade: J55 True Vertical Setting Depth: 1377'
16. Intermed. Casing Size: / Weight per Foot: Grade: True Vertical Setting Depth:

KICK INFORMATION

17. True Vertical Depth at Kick: 8,198	19. Formation Code: NMFK
18. Formation at Kick: Coal Ridge	
20. Shut-in Drill Pipe Pressure (SIDPP): 88 psi.	
21. Shut-in Casing Pressure (SICP): 90 psi.	
22. Mud Weight at Time of Kick: 11.1 ppg.	
23. Pit Gain: 24 bbls.	
24. Time and Date Shut In: 5/7/11 @ 20:08 HRS	
25. Mud Weight Required to Control Well: 11.5 ppg	
26. Type of Kick: <input checked="" type="checkbox"/> Gas <input type="checkbox"/> Oil <input type="checkbox"/> Water	
27. Comments (describe actions to control in detail):	
While circulating on bottom to continue drilling after 40 min flowcheck took 24 bbl gain. Shut-in well and recorded 88 psi SIDPP and 90 psi SICP. Circulate kick out @ 40 SPM and 11.5 ppg KMW. Had no flare and 11.5 ppg MW in and 11.1 ppg MW out. Continue to circulate 2 bottoms up until 11.5 ppg MW in and 11.5 ppg MW out. Lost 174 bbls to seepage. Well dead @ 6:00 hours on 5/8/11	