

CURRENT WELLBORE DIAGRAM

KB	6797 ft.
GL	6775 ft.
Surface csg. CMT to surface	
175 sks Class G	

### CASING RECORD

SIZE (in)	WT (lb/ft)	GRADE	Hole D(in)	TOP (ft)	BTM (ft)	Date Run
8 5/8	24	assumed J-55	12 1/4	0	213	
8 1/2	17	assumed J-55	7 7/8	0	2,352	
5 1/2	15.5	assumed J-55	7 7/8	2,352	3,154	

## TUBING RECORD

SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)	Date Run
2 7/8	8.5	assumed J-55	0	2,829	

## JEWELRY RECORD

[illegible]

## PERFORATION RECORD

ZONE	TOP (ft)	BTM (ft)	SPF	Holes	Date Shot
Mancos B	2714	3037		18	

COMMENTS/HISTORY:

TOC Unknown  
First stage cement:  
200 sks 50-50 poz mix  
Second stage cement:  
100 sks Class G

EOT @ 2,829

PBTD (ft): 3062  
TD (ft): 3208