



CEMENTER'S WELL SERVICE, INC.
P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

198950

Date 2-6-11	Well Owner KERR MCGEE	Well No. 11-2	Lease PEAKS
County WELD	State COLORADO	Field	
Charge to KERR MCGEE OIL+GAS ONSHORE, LP	Charge Code		
Address 1999 BROADWAY, SUITE 3700 (XTREME-12)	For Office Use Only		
City, State DENVER COLORADO 80202			
Pump Truck No. 1202	Code	Bulk Truck No. 1216/1218	Code
Type of Job	Depth	Ft. 935	To
Surface 8 7/8" CSG-24#	Bottom of Surface	Ft. 925	To
Plug	Plug Landed @ 880	Ft. Time On 1600	
Production	Pipe Landed @ 925	Ft. Time Off PLUG DOWN 1815	

Reference No.	Description	Qty.	Meas.	Unit Price	Amount
	Pump Truck Charge				
	Cement Neat TYPE III	580	SKS		
	Poz. Mix		MIKE LINGREEN		
	Calcium Chloride	2.5%	User ID ZMDLG		
	Gel % Flo-Cele 4# Per Sack		WBS/WOCC 2026111		
	Handling Charge		800/2070		
	Hauling Charge				
	Additional Cement				
	MIX RATE 4 BPM	PREFLUSH		1719	-1727
	DISP RATE 5 BPM	MIX		1727	-1801
	SLURRY VOL 1.32 FT³/SK	CHANGE VALVES		1801	-1804
	SLURRY WT 14.8-15 PPG	DISPLACE		1804	-1815
	WATER/CEMENT 6.25 GAL/SK	FINAL LIFT	300 PSI		
	WATER TEMP 68 °F	RUG LANDED @ 1000	PSI		
		TOTAL SLURRY VOL	136 BBL CEMENT		

Remarks: PREFLUSH w/ 30 BBL H2O	Tax Reference Code	Sub Total
DISPLACE w/ 56 BBL H2O	State CO 2.9 %	Tax
CIRCULATE 6 BBL CEMENT	Disc.	Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1202	Pump Truck			70			
1216/1218	Bulk Truck			70			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By **Joe, Josh, Kerry, Evan**

Received By

[Signature]
Customer or His Agent