



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

198982

Date <u>02/17/2011</u>	Well Owner <u>KERR McGEE</u>	Well No. <u>33-2</u>	Lease <u>PEAKS</u>
County <u>WELD</u>	State <u>COLORADO</u>	Field	
Charge to <u>KERR McGEE OIL & GAS ONSHORE, LP</u>			Charge Code
Address <u>1999 BROADWAY, SUITE 3700 (XTREME #12)</u>			For Office Use Only
City, State <u>DENVER COLORADO 80202</u>			
Pump Truck No. <u>1201</u>	Code	Bulk Truck No. <u>1214/1217</u>	Code
Type of Job	Depth	Ft. <u>940</u>	To
Surface <u>5/8 CSG-24"</u>	Bottom of Surface	Ft. <u>930</u>	To
Plug	Plug Landed @ <u>886</u>	Ft.	Time On <u>2000</u>
Production	Pipe Landed @ <u>930</u>	Ft.	Time Off <u>PLUG DOWN 2200</u>

Reference No.	Description	Qty.	Meas.	Unit Price	Amount
	Pump Truck Charge				
	Cement Neat <u>TYPE III</u>	<u>590</u>	<u>WKS LINGREEN</u>		
	Poz. Mix		User ID <u>ZMDL8</u>		
	Calcium Chloride	<u>25%</u>			
	Gel % Flo-Cele <u>1/4</u> #Per Sack		<u>WBS/WO/CC 2026/13 DRI</u>		
	Handling Charge		<u>G/L Acct 800/12070</u>		
	Hauling Charge				
	Additional Cement				
	<u>MIXING RATE - 4BPM</u>		<u>PRE-FLUSH</u>	<u>2114-2120</u>	
	<u>DISP. RATE - 5BPM</u>		<u>MIXING</u>	<u>2120-2146</u>	
	<u>SLURRY VOL - 1.32 CU FT³/SK</u>		<u>CHANGE VALVES</u>	<u>2146-2149</u>	
	<u>SLURRY WT 14.8-15.0 PPG</u>		<u>DISP.</u>	<u>2149-2200</u>	
	<u>WATER/CEMENT - 6.25 GAL/SK</u>		<u>FINAL TEST @ 400 PSI</u>		
	<u>WATER TEMP 68°F</u>				
	<u>TOTAL SLURRY VOL 138.7 BBLS CEMENT</u>				
	<u>LANDED PLUG @ 1000 PSI</u>				

Remarks: <u>PRE-FLUSH W/ 30 BBLS H₂O</u>	Tax Reference Code	Sub Total
<u>DISPLACE W/ 56 BBLS H₂O</u>	State <u>CO 2.9 %</u>	Tax
<u>CIRCULATE 6 BBLS CEMENT</u>	Disc.	Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<u>1201</u>		Pump Truck		<u>88</u>			
<u>1214/1217</u>		Bulk Truck		<u>88/88</u>			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By JIM, OSCAR, STEVE, ADAM

Received By Z. Jell

Customer or His Agent