



**CEMENTER'S WELL SERVICE, INC.**  
P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

**198924**

Date <b>2/5/11</b>	Well Owner <b>KERR McGEE</b>	Well No. <b>7-8</b>	Lease <b>Sater</b>
County <b>Weld</b>	State <b>Colorado</b>	Field	
Charge to <b>KERR McGEE Oil &amp; Gas Onshore, LP</b>			Charge Code
Address <b>1999 Broadway, Suite 3700 (Xtreme #15)</b>			For Office Use Only
City, State <b>Denver, Colorado 80202</b>			
Pump Truck No. <b>1208</b>	Code	Bulk Truck No. <b>1217/1218</b>	Code
Type of Job	Depth	Ft. <b>997</b>	To
Surface <b>8 5/8" C50-24"</b>	Bottom of Surface	Ft. <b>989</b>	To
Plug	Plug Landed @ <b>945</b>	Ft.	Time On <b>1200</b>
Production	Pipe Landed @ <b>989</b>	Ft.	Time Off <b>Plug Down 1530</b>

Reference No.	Description	Qty.	Meas.	Unit Price	Amount		
	Pump Truck Charge						
	Cement Neat <b>✓ Type III 100% Excess</b>	<b>620</b>	<b>SKS</b>				
	Poz. Mix						
	Calcium Chloride	<b>25%</b>					
	Gel % Flo-Cele <b>1/4</b> #Per Sack						
	Handling Charge						
	Hauling Charge						
	Additional Cement	<b>30</b>	<b>SKS</b>				
	Mixing Rate-4 BPM						
	Pre-Flush						
	Disp Rate-5 BPM						
	Mixing						
	Slurry Vol-1.32 CU FT/SK						
	Change Valves						
	Slurry WT 14.8-15.0 PPG						
	Disp.						
	Water/Cement-6.25 Gal/SK						
	Water Temp 75°F						
	Total Slurry Vol 153 BBS Cement						
	Landed Plug @ 410 PSI/FINAL L.F. @ 200 PSI						
Remarks: <b>Pre-Flush w/ 30 BBS H<sup>2</sup>O</b>	Tax Reference Code	Sub Total					
<b>Displace w/ 160 BBS H<sup>2</sup>O</b>	State <b>CO 2.9 %</b>	Tax					
<b>Circulate 2 BBS Cement</b>	Disc.	Total					
Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<b>1208</b>		Pump Truck		<b>64</b>			
<b>1217/1218</b>		Bulk Truck		<b>64/64</b>			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By **Justin Dallas & Steve**

Received By

**Ricky Tuck**

Customer or His Agent