



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

198124

(P.O. # 50576)

Date <u>6/3/10</u>	Well Owner <u>Synergy</u>	Well No. <u>16TD</u>	Lease <u>SRA STATE</u>
County <u>Weld</u>	State <u>Colorado</u>	Field	
Charge to <u>EMSIGN US DRILLING</u>			Charge Code
Address <u>P.O. Box 17805 / EMSIGN #33</u>			For Office Use Only
City, State <u>DENVER Colorado 80217</u>			
Pump Truck No. <u>1208</u>	Code	Bulk Truck No. <u>1207/1216</u>	Code
Type of Job	Depth	Fl. <u>646</u>	To
<u>Surface</u> <u>8 5/8" CSG-24"</u>	Bottom of Surface	Fl. <u>635</u>	To
Plug	Plug Landed @ <u>590</u>	Fl.	Time On <u>1240</u>
Production	Pipe Landed @ <u>635</u>	Fl.	Time Off <u>Plug Down 1430</u>

Reference No.	Description	Qty.	Meas.	Unit Price	Amount		
	Pump Truck Charge						
	Cement Neat ✓	450	SKS		8,570.00		
	Poz. Mix						
	Calcium Chloride	3%					
	Gel % Flo-Cele 1/4 #Per Sack						
	Handling Charge						
	Hauling Charge						
	Additional Cement						
8 5/8"	Centralizers	2		70.00	140.00		
	Cement Basket	2		375.00	750.00		
	Guide Shoe	1			375.00		
	Baffle Plate	1			200.00		
	Box-thread lock	1			30.00		
	Mixing Rate - 4 BPM / Displacement Rate - 4 BPM						
	Slurry Vol - 1.18 CU FT/SK - Slurry wt 15.2 PPG / Water Temp 60°F						
	Total Slurry Vol 94.5 BBLs Cement / Landed Plug 725 PSI						
Remarks: Pre-Flush w/ 20 BBLs H ² O	Tax Reference Code		Sub Total		10,065.00		
Displace w 37.5 BBLs H ² O	State CO 2.9 %		Tax		291.89		
Circulate 10 BBLs Cement	Disc.		Total		10,356.89		
Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1208		Pump Truck		24			
1207/1216		Bulk Truck		24/24			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Justin, Steve & Dallas

Received By [Signature]

Customer or His Agent