



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

199511

Date	4/9/11	Well Owner	Kerr McGee	Well No.	32-21	Lessee	JD
County	Weld	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth	FL 450				
Surface	9 5/8" 154-94"	Bottom of Surface	FL 440				
Plug		Plug Landed @	596	FL	Time On 1930		
Production		Pipe Landed @	640	R.	Plug Down 2115		

Description	Qty	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat	400	SKS		
Pos. Mix				
Calcium Chloride	2.5	%		
Col %	Flo-Cote 1/4 # Per Sack			
Mileage Charge	40	Miles		
Fuel Surcharge	40	Miles		
Additional Cement		SKS		
Mixing Rate	4 BPM	Pre-Flush	2043-	2047
Disp. Rate	5 BPM	Mixing	2047-	2107
Slurry Vol.	1.32 Cu. Ft./Sk	Change Valves	2104-	2107
Slurry Wt.	14.8 - 15.0 PPG	Displacement	2107-	2115
Water/Cement	6.25 Gal/SK			
Water Temp.	64°F			
Total Slurry Vol.	94	BBLs Cement		
Landed Plug @	300	PSI/Final Lift @	100	PSI
Pre-Flush Wt	30	BBLs H ₂ O		Sub Total
Displace Wt	38	BBLs H ₂ O		State CO 2.9%
Circulate	4	BBLs Cement		Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1008		Pump Truck		20			
1017		Bulk Truck		20			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Justin D. Davis & Justin D.

Received By Karl M. M...

Customer or His Agent