

FORM

2

Rev
12/05

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

 OIL ☒ GAS ☐ COALBED ☐ OTHER _____
 SINGLE ZONE ☒ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐

 Refiling ☐
 Sidetrack ☐

Document Number:

400158163

Plugging Bond Surety

20030058

3. Name of Operator: EOG RESOURCES INC4. COGCC Operator Number: 277425. Address: 600 17TH ST STE 1100NCity: DENVER State: CO Zip: 802026. Contact Name: Nanette Lupcho Phone: (435)781-9157 Fax: (435)789-7633Email: nanette_lupcho@eogresources.com7. Well Name: Garden Creek Well Number: 19-27H

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 11354

WELL LOCATION INFORMATION

10. QtrQtr: SESE Sec: 27 Twp: 11N Rng: 62W Meridian: 6Latitude: 40.887481 Longitude: -104.299244
 Footage at Surface: 501 feet FNL/FSL 501 feet FEL/FWL FEL
11. Field Name: Wildcat Field Number: 9999912. Ground Elevation: 5097 13. County: WELD

14. GPS Data:

Date of Measurement: 10/22/2010 PDOP Reading: 1.2 Instrument Operator's Name: Robert Kay15. If well is ☐ Directional ☒ Horizontal (highly deviated) **submit deviated drilling plan.**
 Footage at Top of Prod Zone: FNL/FSL 933 FSL 708 FEL 600 Bottom Hole: FNL/FSL 2505 FEL/FWL FEL
 Sec: 27 Twp: 11N Rng: 62W Sec: 27 Twp: 11N Rng: 62W
16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No17. Distance to the nearest building, public road, above ground utility or railroad: 2476 ft18. Distance to nearest property line: 501 ft 19. Distance to nearest well permitted/completed in the same formation: 1580 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Niobrara	NBRR	421-3	640	All

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: 20090014

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☒ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
Township 11 North Range 62 West of the 6th P. M.: Section 27: All

25. Distance to Nearest Mineral Lease Line: 600 ft 26. Total Acres in Lease: 640

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☐ Land Farming ☐ Land Spreading ☒ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	20	16	42	0	60	50	60	0
SURF	13+1/2	9+5/8	36	0	1,100	575	1,100	0
1ST	8+3/4	7	23	0	7,206	765	7,206	0
1ST LINER	6	4+1/2	11.6	6456	11,354	305	11,354	6,456

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments We have measured the distance to the nearest well in same formation from the Garden Creek 19-27H SHL to the EOG permitted Garden Creek 26-35H BHL, API No. 05-123-32448.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Nanette Lupcho

Title: Regulatory Assistant Date: 5/9/2011 Email: Nanette_Lupcho@eogresource

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Nesline Director of COGCC Date: 5/31/2011

API NUMBER

05 123 33585 00

Permit Number: _____ Expiration Date: 5/30/2013

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- 1) Provide 24 hour notice of MIRU to Bo Brown at e-mail bo.brown@state.co.us.
- 2) Comply with Rule 317.i and provide cement coverage from end of 7" casing to a minimum of 200' above Niobrara. Verify coverage with cement bond log.
- 3) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

Attachment Check List

Att Doc Num	Name
400158163	FORM 2 SUBMITTED
400158331	DRILLING PLAN
400158332	DEVIATED DRILLING PLAN
400158333	PLAT
400158334	TOPO MAP

Total Attach: 5 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)