

FORM
2Rev
12/05State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400170126

Plugging Bond Surety

20100108

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER _____
SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐Refiling ☐
Sidetrack ☐

3. Name of Operator: CARRIZO OIL & GAS INC

4. COGCC Operator Number: 10338

5. Address: 1000 LOUISIANA STREET #1500

City: HOUSTON State: TX Zip: 77002

6. Contact Name: KIMBERLY LONG Phone: (713)328-1000 Fax: (713)328-1060
Email: kimberly.long@crzo.net

7. Well Name: PERGAMOS Well Number: 4-44-7-60

8. Unit Name (if appl): Unit Number:

9. Proposed Total Measured Depth: 12255

WELL LOCATION INFORMATION

10. QtrQtr: SE SE Sec: 4 Twp: 7N Rng: 60W Meridian: 6

Latitude: 40.597610 Longitude: -104.089120

Footage at Surface: 240 feet FNL/FSL FSL 240 feet FEL/FWL FEL

11. Field Name: WILDCAT Field Number: 99999

12. Ground Elevation: 4920 13. County: WELD

14. GPS Data:

Date of Measurement: 03/01/2011 PDOP Reading: 1.8 Instrument Operator's Name: MARC WOODARD

15. If well is ☐ Directional ☒ Horizontal (highly deviated) submit deviated drilling plan.Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL
650 FSL 652 FEL 650 FNL 650 FWL
Sec: 4 Twp: 7N Rng: 60W Sec: 4 Twp: 7N Rng: 60W16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 5280 ft

18. Distance to nearest property line: 240 ft 19. Distance to nearest well permitted/completed in the same formation: 3360 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR			

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#:23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No23b. If 23 is ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard Qtr/Qtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
T7N R60W SECTION 4, E 1/2

25. Distance to Nearest Mineral Lease Line: 650 ft

26. Total Acres in Lease: 960

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☐ Offsite ☒ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Landfarm & Evaporation

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	9+5/8	36	0	1,400	534	1,400	0
1ST	8+3/4	7	23	1400	6,627	631	6,627	1,400
1ST LINER	6+1/8	4+1/2	11.6	5627	12,255	464	12,255	5,627

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments NO CONDUCTOR CASING WILL BE SET. ALL FOOTAGES 5280' ARE ONE MILE OR GREATER. APPLICATION FOR A DRILLING AND SPACING UNIT HAS BEEN MADE AND IS ON THE JUNE 27 AND 28, 2011 DOCKET FOR APPROVAL.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: KIMBERLY LONG

Title: COMPLIANCE SPECIALIST

Date: _____

Email: kimberly.long@crzo.net

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____

Director of COGCC

Date: _____

API NUMBER

05

Permit Number: _____

Expiration Date: _____

CONDITIONS OF APPROVAL, IF ANY: _____

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Attachment Check List

Att Doc Num	Name
400170180	WELL LOCATION PLAT
400170181	DEVIATED DRILLING PLAN

Total Attach: 2 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

BMP

<u>Type</u>	<u>Comment</u>
Material Handling and Spill Prevention	Operator will ensure 110 percent secondary containment for any volume of fluids contained at the well site during drilling and completion. Operator will implement best management practices to contain any unintentional release of fluids.
Storm Water/Erosion Control	Operator has designed the well pad with insloping and a storm water control ditch to prevent storm water run-on/runoff and the release of fluids from the location. See attached Construction Layout Drawing.
Site Specific	Fresh water for the Fresh Water Storage Pit comes from water provider; water sources permitted for consumable industrial use.
Material Handling and Spill Prevention	Operator shall not allow any fluids to flow back to the Fresh Water Storage Pit.
Site Specific	Fresh Water Storage Pit shall contain fresh water only and signage prohibiting the use of the pit for any fluid that does not come from municipal, irrigation or surface water source.
Construction	The location will be fenced and the fenced area will include the Fresh Water Storage Pit.
Pre-Construction	The COGCC to be notified 48 hours prior to construction of the Fresh Water Storage Pit.

Total: 7 comment(s)