

STREAR V06-63 HN
S6, T2N, R67W
SE/4 SE/4
Weld County, CO

Map Unit Description

Weld County, Colorado, Southern Part

0 to 14 inches: loamy sand
14 to 60 inches: loamy sand

Minor Components

Osgood

Percent of map unit: 5 percent

Valent

Percent of map unit: 5 percent

72 Vona loamy sand, 0 to 3 percent slopes

Setting

Elevation: 4600 to 5200 feet
Mean annual precipitation: 13 to 15 inches
Mean annual air temperature: 48 to 55 degrees F
Frost-free period: 130 to 160 days

Composition

Vona and similar soils: 85 percent
Minor components: 15 percent

Description of Vona

Setting

Landform: Terraces, plains
Down-slope shape: Linear
Across-slope shape: Linear
Parent material: Alluvium and/or eolian deposits

Properties and Qualities

Slope: 0 to 3 percent
Drainage class: Well drained
Capacity of the most limiting layer to transmit water (Ksat): High (1.98 to 6.00 in/hr)
Frequency of flooding: None
Frequency of ponding: None
Calcium carbonate maximum: 15 percent
Gypsum maximum: 0 percent
Available water capacity: Moderate (about 6.5 inches)

Interpretive Groups

Land capability classification (irrigated): 3e
Land capability (non irrigated): 4e
Ecological site: Sandy Plains (R067BY024CO)

Typical Profile

0 to 6 inches: loamy sand
6 to 28 inches: fine sandy loam
28 to 60 inches: sandy loam

Minor Components

Remmit

Percent of map unit: 10 percent

Valent

Percent of map unit: 5 percent

Map Unit Description

Weld County, Colorado, Southern Part

STREAR Vole - 63 HN
S 6, T 2N, R 67W
SE/4 SE/4
Weld County, CO

73 Vona loamy sand, 3 to 5 percent slopes

Setting

Elevation: 4600 to 5200 feet
Mean annual precipitation: 13 to 15 inches
Mean annual air temperature: 48 to 55 degrees F
Frost-free period: 130 to 160 days

Composition

Vona and similar soils: 85 percent
Minor components: 15 percent

Description of Vona

Setting

Landform: Terraces, plains
Down-slope shape: Linear
Across-slope shape: Linear
Parent material: Alluvium and/or eolian deposits

Properties and Qualities

Slope: 3 to 5 percent
Drainage class: Well drained
Capacity of the most limiting layer to transmit water (Ksat): High (1.98 to 6.00 in/hr)
Frequency of flooding: None
Frequency of ponding: None
Calcium carbonate maximum: 15 percent
Gypsum maximum: 0 percent
Available water capacity: Moderate (about 6.5 inches)

Interpretive Groups

Land capability classification (irrigated): 3e
Land capability (non irrigated): 4e
Ecological site: Sandy Plains (R067BY024CO)

Typical Profile

0 to 6 inches: loamy sand
6 to 28 inches: fine sandy loam
28 to 60 inches: sandy loam

Minor Components

Remmit

Percent of map unit: 8 percent

Valent

Percent of map unit: 7 percent