

FORM 5A Rev 02/08

State of Colorado Oil and Gas Conservation Commission 1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



Table with columns DE, ET, OE, ES

Document Number: 2591830

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 8960 4. Contact Name: KERRY MCCOWEN
2. Name of Operator: BONANZA CREEK ENERGY OPERATING COMPAN Phone: (720) 279-2330
3. Address: P O BOX 21974 Fax: (720) 279-2331
City: BAKERSFIELD State: CA Zip: 93390

5. API Number 05-123-31828-00 6. County: WELD
7. Well Name: Antelope Well Number: 14-18
8. Location: QtrQtr: NESW Section: 18 Township: 5N Range: 62W Meridian: 6
9. Field Name: WATTENBERG Field Code: 90750

Completed Interval

FORMATION: NIOBRARA-CODELL Status: PRODUCING

Treatment Date: 10/08/2010 Date of First Production this formation: 11/14/2010

Perforations Top: 6316 Bottom: 6578 No. Holes: 100 Hole size: 40/100

Provide a brief summary of the formation treatment: Open Hole: [ ]

CODL PUMPED 32004 GAL FLUID AND 97734 HAL PHASERFRAC WITH 245220 LBS 20/40 SAND. ISDP 3019 PSI; ATR 23.7 BPM; ATP 3532 PSI. NBRR PUMPED 25914 GAL PAD FLUID AND 111804 GAL PHASERFRAC WITH 261440 LBS 30/50 SAND. ISDP 3074 PSI; ATR 52.2 BPM; ATP 3894 PSI

This formation is commingled with another formation: [X] Yes [ ] No

Test Information:

Date: 12/11/2010 Hours: 24 Bbls oil: 59 Mcf Gas: 63 Bbls H2O: 20

Calculated 24 hour rate: Bbls oil: 59 Mcf Gas: 63 Bbls H2O: 20 GOR: [ ]

Test Method: FLOWING Casing PSI: 300 Tubing PSI: [ ] Choke Size: [ ]

Gas Disposition: SOLD Gas Type: WET BTU Gas: 1300 API Gravity Oil: 42

Tubing Size: [ ] Tubing Setting Depth: [ ] Tbg setting date: [ ] Packer Depth: [ ]

Reason for Non-Production: [ ]

Date formation Abandoned: [ ] Squeeze: [ ] Yes [ ] No If yes, number of sacks cmt [ ]

Bridge Plug Depth: [ ] Sacks cement on top: [ ]

Comment: [ ]

**IMPORTANT: SOME DATA FIELDS HAVE BEEN MODIFIED.**

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: KERRY MCCOWEN

Title: V.P. OPERATIONS Date: 12/15/2010 Email KAM@BONANZACRK.COM  
:

**Attachment Check List**

Att Doc Num	Name
2591830	FORM 5A SUBMITTED
2591831	WELLBOORE DIAGRAM

Total Attach: 2 Files

**General Comments**

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)