



02055134



State of Colorado Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 (303) 894-2100 Fax: (303) 894-2109



RECEIVED

MAY 30 2011

COGCC

LOSS OF WELL CONTROL REPORT

As required by Rule 327.

1. OGCC Operator Number: 96850	4. Contact Name & Phone Bob Caughlin	Report taken by: Mike Shults DAVE ANDREWS
2. Name of Operator: Williams Production RMT	Ph: 970-589-0673	
3. Address: 1058 County Road 215 City: Parachute State: Co. Zip: 81650	Fax:	

WELL LOCATION INFORMATION

5. API Number: 05-045-19994-00	6. County: Garfield
7. Well Name: SR 44-9	8. Well Number: SR 44-9
9. Unit Name (if appl.):	10. Unit No:
11. Qtr: NWSE Sec: 9 Twp: 7S Rng: 94W Meridian: 6	
12. Footage From Exterior Section Lines: 925' 1654 FSL, 1550 FEL	
13. Field Name: Rulison	14. Field Number: 75400

CASING INFORMATION

15. Surface Casing Size: 9.625 / Weight per Foot: 32.30 Grade: H-40 True Vertical Setting Depth: 1141
16. Intermed. Casing Size: / Weight per Foot: Grade: True Vertical Setting Depth:

KICK INFORMATION

17. True Vertical Depth at Kick: 8429	19. Formation Code: Williams Fork
18. Formation at Kick: Cameo Coal	
20. Shut-in Drill Pipe Pressure (SIDPP): 0 psi.	
21. Shut-in Casing Pressure (SICP): 0 psi.	
22. Mud Weight at Time of Kick: 9.4 ppg.	
23. Pit Gain: 56 bbls.	
24. Time and Date Shut In: 5/29/2011 @ 13:35 hrs.	
25. Mud Weight Required to Control Well: 10.3 ppg.	
26. Type of Kick: <input checked="" type="checkbox"/> Gas <input type="checkbox"/> Oil <input type="checkbox"/> Water	
27. Comments (describe actions to control in detail): Lost circulation 8394' - Pulled out of hole to 6100' and establish circulation bypassed shakers and build volume and mix LCM to 20%. Stage back in hole with full returns. Drilled to 8499' took 56 bbls gain at bottoms up from trip. Shut well in and circulated out gas with the drillers method through the choke manifold raised mud weight to 10.3 ppg. Shut down and checked for flow none observed open Annular and continue circulating and conditioning mud to 10.3 ppg.	