

21. Mineral Ownership: Fee State Federal Indian Lease #: _____

22. Surface Ownership: Fee State Federal Indian

23. Is the Surface Owner also the Mineral Owner? Yes No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? Yes No

23b. If 23 is No: Surface Owners Agreement Attached or \$25,000 Blanket Surface Bond \$2,000 Surface Bond \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
 T10S, R55W, Sec. 18: All; Sec. 20: NE1/4, SW1/4; Sec. 28: W1/2E1/2, W1/2; Sec. 32: SE1/4; T10S, R56W, Sec. 26: N1/2

25. Distance to Nearest Mineral Lease Line: 660 ft 26. Total Acres in Lease: 1917

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? Yes No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? Yes No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? Yes No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? Yes No

31. Mud disposal: Offsite Onsite **If 28, 29, or 30 are "Yes" a pit permit may be required.**

Method: Land Farming Land Spreading Disposal Facility Other: Backfill when dry

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	8+5/8	24	0	300	250	300	0
1ST	7+7/8	5+1/2	17	0	7,900	300	7,900	6,500
S.C. 1.1							4,550	4,000

32. BOP Equipment Type: Annular Preventer Double Ram Rotating Head None

33. Comments No Conductor casing will be used

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan? Yes No

36. Is this application part of submitted Oil and Gas Location Assessment? Yes No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Jack Fincham

Title: Agent Date: 5/4/2011 Email: fincham4@msn.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Nashin Director of COGCC Date: 6/7/2011

API NUMBER
05 073 06454 00

Permit Number: _____ Expiration Date: 6/6/2013

CONDITIONS OF APPROVAL, IF ANY: _____

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- 1) Provide 24 hour notice of MIRU to Craig Quint at 719-767-8939 or e-mail at craig.quint@state.co.us.
- 2) If production casing is set provide cement coverage to at least 200' above CHRK, and stage cement Cheyenne/Dakota interval (4550'-4000' minimum). Run and submit CBL to verify cemented intervals.
- 3) If well is a dry hole set plugs at the following depths: 40 sks cement +/- 50' above the Cherokee, 40 sks cement across any DST w/ show, 40 sks cement 50' below Cheyenne (4600' up), 40 sks cement 50' above top of Dakota (3950' up), 50 sks cement from 50' below surface casing shoe up into surface casing, 15 sks cement in top of surface casing, cut 4 ft below GL, weld on plate, 5 sks cement each in rat hole and mouse hole.

Attachment Check List

Att Doc Num	Name
400161326	FORM 2 SUBMITTED
400161343	WELL LOCATION PLAT
400161344	30 DAY NOTICE LETTER
400161345	SURFACE AGRMT/SURETY
400161349	TOPO MAP
400161351	OTHER
400161353	PROPOSED BMPs

Total Attach: 7 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

BMP

<u>Type</u>	<u>Comment</u>
Material Handling and Spill Prevention	Spill Prevention, Control and Countermeasure Plan is on file in Wiepking-Fullerton Energy, L.L.C. office.

Storm Water/Erosion Control	<p>BMP Plan</p> <p>Wiepking-Fullerton Energy, L.L.C. 4600 S. Downing St. Englewood, CO 80113 303-789-1798 303-761-9067 (fax)</p> <p>Certification to Discharge Under CDPS General Permit COR-03000 Stormwater Discharges Associated with Construction</p> <p>Certification Number COR 39788</p> <p>Kerry # 6 well T10S, R55W Sec. 20: SW1/4NE1/4 Lincoln County, Colorado</p> <p>Description of Well Site and Construction Area 1-3 acre site with access road for drilling of oil and gas well. Terrain is flat with native grass and sagebrush. No receiving waters will be affected by well pad. Silt fences will be installed on low side site of drill site. Drilling pits closed and reclaimed with the drillsite. Topsoil will be separated and spread on drill site as final operation before reseeding operations which will be completed within 6 months weather permitting. To prevent soil erosion site will be disked and straw crimped in or manure spread.</p> <p>Stormwater Management Plan (SWMP) is on file in Wiepking-Fullerton Energy, L.L.C. office.</p> <p>Spill Prevention, Control and Countermeasure Plan is on file in Wiepking-Fullerton Energy, L.L.C. office.</p>
Construction	<p>Description of Well Site and Construction Area 1-3 acre site with access road for drilling of oil and gas well. Terrain is flat with native grass and sagebrush. No receiving waters will be affected by well pad. Silt fences will be installed on low side site of drill site. Drilling pits closed and reclaimed with the drillsite. Topsoil will be separated and spread on drill site as final operation before reseeding operations which will be completed within 6 months weather permitting. To prevent soil erosion site will be disked and straw crimped in or manure spread.</p>

Total: 3 comment(s)