


<b>FORM</b> <b>2</b> Rev 12/05	<b>State of Colorado</b> <b>Oil and Gas Conservation Commission</b> 1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109		<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 25%;">DE</td> <td style="width: 25%;">ET</td> <td style="width: 25%;">OE</td> <td style="width: 25%;">ES</td> </tr> </table>	DE	ET	OE	ES
DE	ET	OE	ES				
<b>APPLICATION FOR PERMIT TO:</b>			Document Number:  400163199  Plugging Bond Surety  20100017				
1. <input checked="" type="checkbox"/> <b>Drill,</b> <input type="checkbox"/> Deepen, <input type="checkbox"/> Re-enter, <input type="checkbox"/> Recomplete and Operate							
2. TYPE OF WELL OIL <input type="checkbox"/> GAS <input checked="" type="checkbox"/> COALBED <input type="checkbox"/> OTHER _____ SINGLE ZONE <input checked="" type="checkbox"/> MULTIPLE ZONE <input type="checkbox"/> COMMINGLE ZONE <input type="checkbox"/>		Refiling <input type="checkbox"/> Sidetrack <input type="checkbox"/>					
3. Name of Operator: <u>ENCANA OIL &amp; GAS (USA) INC</u>		4. COGCC Operator Number: <u>100185</u>					
5. Address: <u>370 17TH ST STE 1700</u> City: <u>DENVER</u> State: <u>CO</u> Zip: <u>80202-5632</u>							
6. Contact Name: <u>MIRACLE PFISTER</u> Phone: <u>(720)876-3761</u> Fax: <u>(720)876-4861</u> Email: <u>miracle.pfister@encana.com</u>							
7. Well Name: <u>ENCANA FEE</u>		Well Number: <u>24-8B1 (K19CNE)</u>					
8. Unit Name (if appl): <u>GRASS MESA</u>		Unit Number: <u>COC 56608X</u>					
9. Proposed Total Measured Depth: <u>8778</u>							
<b>WELL LOCATION INFORMATION</b>							
10. QtrQtr: <u>LOT 3</u> Sec: <u>19</u> Twp: <u>6S</u> Rng: <u>92W</u> Meridian: <u>6</u> Latitude: <u>39.511319</u> Longitude: <u>-107.713796</u>							
Footage at Surface: <u>2370</u> feet      FNL/FSL <u>FSL</u> <u>321</u> feet      FEL/FWL <u>FWL</u>							
11. Field Name: <u>MAMM CREEK</u>		Field Number: <u>52500</u>					
12. Ground Elevation: <u>5670</u>		13. County: <u>GARFIELD</u>					
14. GPS Data: Date of Measurement: <u>11/08/2010</u> PDOP Reading: <u>2.4</u> Instrument Operator's Name: <u>C.D SLAUGH</u>							
15. If well is <input type="checkbox"/> Directional <input type="checkbox"/> Horizontal (highly deviated) <b>submit deviated drilling plan.</b> Footage at Top of Prod Zone:      FNL/FSL      FEL/FWL      Bottom Hole:      FNL/FSL      FEL/FWL <u>1500</u> <u>FNL</u> <u>845</u> <u>FEL</u> <u>1500</u> <u>FNL</u> <u>845</u> <u>FEL</u> Sec: <u>24</u> Twp: <u>6S</u> Rng: <u>93W</u> Sec: <u>24</u> Twp: <u>6S</u> Rng: <u>93W</u>							
16. Is location in a high density area? (Rule 603b)? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No							
17. Distance to the nearest building, public road, above ground utility or railroad: <u>1012 ft</u>							
18. Distance to nearest property line: <u>228 ft</u> 19. Distance to nearest well permitted/completed in the same formation: <u>270 ft</u>							
<b>20. LEASE, SPACING AND POOLING INFORMATION</b>							
Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)			
WILLIAMS FORK	WMFK						

**IMPORTANT: SOME DATA FIELDS HAVE BEEN MODIFIED.**

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: \_\_\_\_\_

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
6S-93W SEC 23: NESE SEC 24: N2, NWSW, E2SE, LESS AND EXCEpT An ESTIMATED 4.006 ACRE TRACT AND A 33.34 ACRE TRACT IN THE N2. SEC 25: E2NE, SWNE, SE

25. Distance to Nearest Mineral Lease Line: 240 ft 26. Total Acres in Lease: 627

**DRILLING PLANS AND PROCEDURES**

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☐ Offsite ☒ Onsite **If 28, 29, or 30 are "Yes" a pit permit may be required.**

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: \_\_\_\_\_

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	24	16	LINEPIPE	0	40	5	40	0
SURF	12+1/4	9+5/8	36	0	1,319	412	1,319	0
1ST	7+7/8	4+1/2	11.6	0	8,778	611	8,778	0

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments THE NEAREST DISTANCE IS TO A PUBLIC ROAD. THIS IS ENCANA SURFACE AND NO SDA OR 30 DAY LETTER IS ATTACHED. TOP OF CEMENT FOR THE PRODUCTION CASING IS 500 FT ABOVE TOP OF GAS.

34. Location ID: 335409

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: MIRACLE PFISTER

Title: REGULATORY ANALYST Date: 5/11/2011 Email: miracle.pfister@encana.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Nesline Director of COGCC Date: 6/8/2011

**API NUMBER**

05 045 20768 00

Permit Number: \_\_\_\_\_ Expiration Date: 6/7/2013

**CONDITIONS OF APPROVAL, IF ANY:**

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

(1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.

(2) GARFIELD COUNTY RULISON-FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE.

(3) NEW MAMM CREEK FIELD NOTICE TO OPERATORS APPLIES TO THIS WELL. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE.

(4) COMPLIANCE WITH THE NOTICE TO OPERATORS DRILLING WELLS IN THE BUZZARD, MAMM CREEK, AND RULISON FIELDS, GARFIELD COUNTY AND MESA COUNTY IS REQUIRED. SEE ATTACHED NOTICE.

(5) NO PORTION OF ANY PIT THAT WILL BE USED TO HOLD LIQUIDS SHALL BE CONSTRUCTED ON FILL MATERIAL, UNLESS THE PIT AND FILL SLOPE ARE DESIGNED AND CERTIFIED BY A PROFESSIONAL ENGINEER, SUBJECT TO REVIEW AND APPROVAL BY THE DIRECTOR PRIOR TO CONSTRUCTION OF THE PIT. THE CONSTRUCTION AND LINING OF THE PIT SHALL BE SUPERVISED BY A PROFESSIONAL ENGINEER OR THEIR AGENT. THE ENTIRE BASE OF THE PIT MUST BE IN CUT.

(6) THE SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1-MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1-MILE IS 400 FEET DEEP.

### **Attachment Check List**

Att Doc Num	Name
400163199	FORM 2 SUBMITTED
400163720	DEVIATED DRILLING PLAN
400163721	PLAT

Total Attach: 3 Files

### **General Comments**

<b><u>User Group</u></b>	<b><u>Comment</u></b>	<b><u>Comment Date</u></b>

Total: 0 comment(s)

### **BMP**

<b><u>Type</u></b>	<b><u>Comment</u></b>

Total: 0 comment(s)