


<b>FORM</b> <b>2</b> Rev 12/05	<b>State of Colorado</b> <b>Oil and Gas Conservation Commission</b> 1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109		<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 25%;">DE</td> <td style="width: 25%;">ET</td> <td style="width: 25%;">OE</td> <td style="width: 25%;">ES</td> </tr> </table> Document Number:  400159580  Plugging Bond Surety	DE	ET	OE	ES
DE	ET	OE	ES				
<b>APPLICATION FOR PERMIT TO:</b>							
1. <input checked="" type="checkbox"/> <b>Drill,</b> <input type="checkbox"/> Deepen, <input type="checkbox"/> Re-enter, <input type="checkbox"/> Recomplete and Operate							
2. TYPE OF WELL OIL <input type="checkbox"/> GAS <input checked="" type="checkbox"/> COALBED <input type="checkbox"/> OTHER _____ SINGLE ZONE <input checked="" type="checkbox"/> MULTIPLE ZONE <input type="checkbox"/> COMMINGLE ZONE <input type="checkbox"/>		Refiling <input type="checkbox"/> Sidetrack <input type="checkbox"/>					
3. Name of Operator: <u>WILLIAMS PRODUCTION RMT COMPANY LLC</u> 4. COGCC Operator Number: <u>96850</u>							
5. Address: <u>1001 17TH STREET - SUITE #1200</u> City: <u>DENVER</u> State: <u>CO</u> Zip: <u>80202</u>							
6. Contact Name: <u>Greg Davis</u> Phone: <u>(303)606-4071</u> Fax: <u>(303)629-8268</u> Email: <u>Greg.J.Davis@Williams.com</u>							
7. Well Name: <u>Hoepli</u> Well Number: <u>RWF 411-36</u>							
8. Unit Name (if appl): _____      Unit Number: _____							
9. Proposed Total Measured Depth: <u>8955</u>							
<b>WELL LOCATION INFORMATION</b>							
10. QtrQtr: <u>SENW</u> Sec: <u>36</u> Twp: <u>6S</u> Rng: <u>94W</u> Meridian: <u>6</u> Latitude: <u>39.485198</u> Longitude: <u>-107.839946</u>							
Footage at Surface: <u>1551</u> feet      FNL/FSL <u>FNL</u> 1699 feet      FEL/FWL <u>FWL</u>							
11. Field Name: <u>Rulison</u> Field Number: <u>75400</u>							
12. Ground Elevation: <u>6387</u> 13. County: <u>GARFIELD</u>							
14. GPS Data: Date of Measurement: <u>11/04/2010</u> PDOP Reading: <u>1.7</u> Instrument Operator's Name: <u>J. Kirkpatrick</u>							
15. If well is <input checked="" type="checkbox"/> Directional <input type="checkbox"/> Horizontal (highly deviated) <b>submit deviated drilling plan.</b> Footage at Top of Prod Zone:      FNL/FSL      FEL/FWL      Bottom Hole:      FNL/FSL      FEL/FWL <u>392</u> <u>FNL</u> <u>614</u> <u>FWL</u> <u>392</u> <u>FNL</u> <u>614</u> <u>FWL</u> Sec: <u>36</u> Twp: <u>6S</u> Rng: <u>94W</u> Sec: <u>36</u> Twp: <u>6S</u> Rng: <u>94W</u>							
16. Is location in a high density area? (Rule 603b)? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No							
17. Distance to the nearest building, public road, above ground utility or railroad: <u>1614 ft</u>							
18. Distance to nearest property line: <u>332 ft</u> 19. Distance to nearest well permitted/completed in the same formation: <u>363 ft</u>							
<b>20. LEASE, SPACING AND POOLING INFORMATION</b>							
Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)			
Williams Fork	WMFK	139-66	640	All			

**IMPORTANT: SOME DATA FIELDS HAVE BEEN MODIFIED.**

21. Mineral Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian Lease #: COC07506

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☒ No

23b. If 23 is No: ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
See attached.

25. Distance to Nearest Mineral Lease Line: 392 ft 26. Total Acres in Lease: 1595

**DRILLING PLANS AND PROCEDURES**

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☐ Offsite ☒ Onsite **If 28, 29, or 30 are "Yes" a pit permit may be required.**

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Re-use and evaporation

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	24	18	48#	0	45	25	45	0
SURF	13+1/2	9+5/8	32.3#	0	1,127	297	1,127	0
1ST	7+7/8	4+1/2	11.6#	0	8,955	710	8,955	

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments Closed Loop. Cement 200' above uppermost mesaverde sand. See Williams Master APD. CA COC53640

34. Location ID: 335486

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Greg Davis

Title: Supervisor Permits Date: 5/6/2011 Email: Greg.J.Davis@Williams.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 6/8/2011

**API NUMBER**

05 045 20774 00

Permit Number: \_\_\_\_\_ Expiration Date: 6/7/2013

**CONDITIONS OF APPROVAL, IF ANY:**

**All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.**

(1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.

(2) GARFIELD COUNTY RULISON-FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE.

(3) THE MOISTURE CONTENT OF ANY DRILL CUTTINGS IN A CUTTINGS PIT, TRENCH, OR PILE SHALL BE AS LOW AS PRACTICABLE TO PREVENT ACCUMULATION OF LIQUIDS GREATER THAN DE-MINIMIS AMOUNTS. AT THE TIME OF CLOSURE, THE DRILL CUTTINGS MUST ALSO MEET THE APPLICABLE STANDARDS OF TABLE 910-1.

(4) NO PORTION OF ANY PIT THAT WILL BE USED TO HOLD LIQUIDS SHALL BE CONSTRUCTED ON FILL MATERIAL, UNLESS THE PIT AND FILL SLOPE ARE DESIGNED AND CERTIFIED BY A PROFESSIONAL ENGINEER, SUBJECT TO REVIEW AND APPROVAL BY THE DIRECTOR PRIOR TO CONSTRUCTION OF THE PIT. THE CONSTRUCTION AND LINING OF THE PIT SHALL BE SUPERVISED BY A PROFESSIONAL ENGINEER OR THEIR AGENT. THE ENTIRE BASE OF THE PIT MUST BE IN CUT.

(5) THE SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1-MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1-MILE IS 271 FEET DEEP.

### **Attachment Check List**

Att Doc Num	Name
400159580	FORM 2 SUBMITTED
400159583	DEVIATED DRILLING PLAN
400159883	WELL LOCATION PLAT
400159885	TOPO MAP
400159886	LEGAL/LEASE DESCRIPTION
400160476	SURFACE AGRMT/SURETY
400162602	FED. DRILLING PERMIT

Total Attach: 7 Files

### **General Comments**

User Group	Comment	Comment Date
Permit	Changed application to reflect surface owner is not mineral owner	6/6/2011 11:28:04 AM
Permit	Surface & Mineral ownership added (matched with other wells on this pad) and Opr Greg noticed; and permit moved to In Process according to direction by R. E.	5/11/2011 9:09:54 AM
Permit	Back to Draft Surface owner and mineral owner information missing	5/9/2011 2:56:35 PM

Total: 3 comment(s)

### **BMP**

Type	Comment

Total: 0 comment(s)