



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 355-7299 • FAX (970) 353-7712

OUR INVOICE

199524

Date	4/7/2011	Well Owner	Kerr McGee	Well No.	36-27	Lease	WILD PUCKER
County	Weld	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (PATTERSON th 199)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth	ft. 825				
Surface	8 5/8" Csg 24"	Bottom of Surface	ft. 815				
Plug		Plug Landed @	769	ft.	Time On	1130	
Production		Pipe Landed @	815	ft.	Plug Down	1345	

Description	Qty	Meas	Unit Price	Amount
Set Up Charge	1			
Cement Neat	TYPE III	510	SKS	
Poz. Mla				
Calcium Chloride		2.5	%	
Gel %	File-Cats 1/4 # Per Sack			
Mileage Charge	800/2410	282	Miles	
Fuel Surcharge		282	miles	
Additional Cement			SKS	
Mixing Rate	4 BPM	Pre-Flush	1305	1309
Disp. Rate	5 BPM	Mixing	1309	1332
Slurry Vol	1.32" Cu Ft/SK	Change Valves	1332	1335
Slurry Wt	14.8 - 15.0 PPG	Displacement	1335	1345
Water/Cement	6.25 Gal/SK			
Water Temp.	53			
Total Slurry Vol	119.8	BBLs Cement		
Landed Plug @	390	PSI/Final Lift @	240	PSI
Pre-Flush Wt	20	BBLs H ₂ O	Tax Reference Code	Sub Total
Displace Wt	49	BBLs H ₂ O	State	CO 2.9%
Choclate	6	BBLs Cement		Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1261	Pump Truck			94			
1215/1217	Bulk Truck			94/94			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Jim Lindem/Steve

Received By

Customer or His Agent