

APPLICATION FOR PERMIT TO:

1. Drill, Deepen, Re-enter, Recomplete and Operate

2. TYPE OF WELL
 OIL GAS COALBED OTHER _____
 SINGLE ZONE MULTIPLE COMMINGLE
 Refiling
 Sidetrack
 Document Number: 400128456
 Plugging Bond Surety: 20030009

3. Name of Operator: NOBLE ENERGY INC 4. COGCC Operator Number: 100322
 5. Address: 1625 BROADWAY STE 2200
 City: DENVER State: CO Zip: 80202
 6. Contact Name: JAN KAJIWARA Phone: (303)228-4092 Fax: (303)228-4286
 Email: jkajiwara@nobleenergyinc.com
 7. Well Name: Boulter PC Well Number: G11-20D
 8. Unit Name (if appl): _____ Unit Number: _____
 9. Proposed Total Measured Depth: 7730

WELL LOCATION INFORMATION

10. QtrQtr: SWSW Sec: 11 Twp: 4n Rng: 65W Meridian: 6
 Latitude: 40.321050 Longitude: -104.635470
 Footage at Surface: 471 feet FNL/FSL 1154 feet FEL/FWL FWL
 11. Field Name: Wattenberg Field Number: 90750
 12. Ground Elevation: 4683 13. County: WELD

14. GPS Data:
 Date of Measurement: 01/01/2011 PDOP Reading: 1.6 Instrument Operator's Name: BRIAN T BRINKMAN

15. If well is Directional Horizontal (highly deviated) **submit deviated drilling plan.**
 Footage at Top of Prod Zone: FNL/FSL 2550 FNL 1320 FWL FWL Bottom Hole: FNL/FSL 2550 FNL 1320 FWL FWL
 Sec: 11 Twp: 4N Rng: 65W Sec: 11 Twp: 4N Rng: 65W

16. Is location in a high density area? (Rule 603b)? Yes No
 17. Distance to the nearest building, public road, above ground utility or railroad: 251 ft
 18. Distance to nearest property line: 151 ft 19. Distance to nearest well permitted/completed in the same formation: 811 ft

LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Codell	CODL	407-87	160	GWA
Niobrara	NBRR	407-87	160	GWA

21. Mineral Ownership: Fee State Federal Indian Lease #: _____
 22. Surface Ownership: Fee State Federal Indian
 23. Is the Surface Owner also the Mineral Owner? Yes No Surface Surety ID#: 20030012
 23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? Yes No

23b. If 23 is No: Surface Owners Agreement Attached or \$25,000 Blanket Surface Bond \$2,000 Surface Bond \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

T4N-R65W Sec. 11: N/2

25. Distance to Nearest Mineral Lease Line: 91 ft 26. Total Acres in Lease: 320

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? Yes No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? Yes No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? Yes No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? Yes No

31. Mud disposal: Offsite Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: Land Farming Land Spreading Disposal Facility Other: Closed Loop

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	8+5/8	24	0	650	230	650	
1ST	7+7/8	4+1/2	11.6	0	7,730	728	7,730	

32. BOP Equipment Type: Annular Preventer Double Ram Rotating Head None

33. Comments Conductor casing won't be used for this well. 1st String TOC = 200 ft above Niobrara. Pad with Boulter PC G11-33D, 14-28D. SEE SAVAGE AND SAVAGE REPORT ON WETLAND DELINEATION (ATTACHED). UNIT CONFIGURATION = Sec. 11 S/2NW/4, N/2SW/4

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? Yes No

36. Is this application part of submitted Oil and Gas Location Assessment ? Yes No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: JAN KAJIWARA

Title: Regulatory Analyst Date: _____ Email: jkajiwara@nobleenergyinc.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

API NUMBER

05

Permit Number: _____ Expiration Date: _____

CONDITIONS OF APPROVAL, IF ANY: _____

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Attachment Check List

Att Doc Num	Name
400135916	WELL LOCATION PLAT
400135917	30 DAY NOTICE LETTER
400135918	EXCEPTION LOC WAIVERS
400135929	DEVIATED DRILLING PLAN
400165353	EXCEPTION LOC REQUEST
400165357	PROPOSED SPACING UNIT

Total Attach: 6 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

BMP

<u>Type</u>	<u>Comment</u>
Storm Water/Erosion Control	Stormwater management plans (SWMP) are in place to address construction, drilling and operations associated with Oil & Gas development throughout the state of Colorado in accordance with Colorado Department of Public Health and Environment (CDPHE) General Permit No. COR-039527. BMP's will be constructed around the perimeter of the site prior to, or at the beginning of construction. BMP's used will vary according to the location, and will remain in place until the pad reaches final reclamation.
Material Handling and Spill Prevention	Spill Prevention Control and Countermeasures (SPCC) plans are in place to address any possible spill associated with Oil & Gas operations throughout the state of Colorado in accordance with CFR 112.
General Housekeeping	Housekeeping will consist of neat and orderly storage of materials and fluids. Wastes will be temporarily stored in sealed containers and regularly collected and disposed of at offsite, suitable facilities. If spills occur prompt cleanup is required to minimize any commingling of waste materials with stormwater runoff. Routine maintenance will be limited to fueling and lubrication of equipment. Drip pans will be used during routine fueling and maintenance to contain spills or leaks. Any waste product from maintenance will be containerized and transported offsite for disposal or recycling. There will be no major equipment overhauls conducted onsite. Equipment will be transported offsite for major overhauls. Cleanup of trash and discarded materials will be conducted at the end of each work day. Cleanup will consist of patrolling the roadway, access areas, and other work areas to pickup trash, scrap debris, other discarded materials, and any contaminated soil. These materials will be disposed of properly.

Total: 3 comment(s)