

FORM
5A

Rev
02/08

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400156371

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 100322 4. Contact Name: Justin Garrett
2. Name of Operator: NOBLE ENERGY INC Phone: (303) 228-4449
3. Address: 1625 BROADWAY STE 2200 Fax: (303) 228-4286
City: DENVER State: CO Zip: 80202

5. API Number 05-123-30895-00 6. County: WELD
7. Well Name: IGO FARMS J Well Number: 28-31D
8. Location: QtrQtr: SWNW Section: 28 Township: 5N Range: 66W Meridian: 6
9. Field Name: WATTENBERG Field Code: 90750

Completed Interval

FORMATION: NIOBARRA-CODELL Status: PRODUCING

Treatment Date: 02/10/2011 Date of First Production this formation: 02/11/2011
Perforations Top: 7115 Bottom: 7446 No. Holes: 104 Hole size:

Provide a brief summary of the formation treatment: Open Hole: ☐

Codell & Niobrara are commingled; the Codell is producing through a composite flow through plug
Codell 7432'-7446', 56 holes, .41"
Frac'd Codell w/117198 gals Silverstim, Acid, and Slick Water with 244000 lbs Ottawa sand
Niobrara 7115'-7256', 48 holes, .69"
Frac'd Niobrara w/154436 gals Silverstim and Slick Water with 249000 lbs Ottawa sand

This formation is commingled with another formation: ☐ Yes ☒ No

Test Information:

Date: 02/15/2011 Hours: 24 Bbls oil: 14 Mcf Gas: 15 Bbls H2O: 50
Calculated 24 hour rate: Bbls oil: 14 Mcf Gas: 15 Bbls H2O: 50 GOR: 1071
Test Method: Flowing Casing PSI: 200 Tubing PSI: 0 Choke Size: 20/64
Gas Disposition: SOLD Gas Type: WET BTU Gas: 1285 API Gravity Oil: 60
Tubing Size: Tubing Setting Depth: Tbg setting date: Packer Depth:

Reason for Non-Production:

Date formation Abandoned: Squeeze: ☐ Yes ☐ No If yes, number of sacks cmt

Bridge Plug Depth: Sacks cement on top:

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Justin Garrett

Title: Regulatory Specialist

Date: 4/28/2011

Email: JDGarrett@nobleenergyinc.com

:

Attachment Check List

Att Doc Num	Name
400156371	FORM 5A SUBMITTED

Total Attach: 1 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)