

FORM

2

Rev
12/05

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400173272

Plugging Bond Surety

20030058

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER _____
 SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refiling ☐Sidetrack ☐3. Name of Operator: EOG RESOURCES INC4. COGCC Operator Number: 277425. Address: 600 17TH ST STE 1100NCity: DENVER State: CO Zip: 802026. Contact Name: Nanette Lupcho Phone: (435)781-9157 Fax: (435)789-7633Email: nanette_lupcho@eogresources.com7. Well Name: Randall Creek Well Number: 12-21H

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 11383

WELL LOCATION INFORMATION

10. QtrQtr: LOT 3 Sec: 21 Twp: 12N Rng: 62W Meridian: 6Latitude: 41.000836 Longitude: -104.324392

Footage at Surface: 637 feet FNL/FSL 2549 feet FEL/FWL
 FNL FWL

11. Field Name: Wildcat Field Number: 9999912. Ground Elevation: 5337 13. County: WELD

14. GPS Data:

Date of Measurement: 04/28/2011 PDOP Reading: 1.5 Instrument Operator's Name: Robert L Kay15. If well is ☐ Directional ☒ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 1064 FNL 2444 FEL 600 FSL 600 FEL
 Bottom Hole: FNL/FSL 600 FSL 600 FEL
 Sec: 21 Twp: 12N Rng: 62W Sec: 21 Twp: 12N Rng: 62W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No17. Distance to the nearest building, public road, above ground utility or railroad: 4549 ft18. Distance to nearest property line: 301 ft 19. Distance to nearest well permitted/completed in the same formation: 5000 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Niobrara	NBRR	421-1	640	ALL

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: _____23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

25. Distance to Nearest Mineral Lease Line: 600 ft

26. Total Acres in Lease: 4491

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☐ Land Spreading ☒ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	20	16	42	0	60	50	60	0
SURF	13+1/2	9+5/8	36	0	1,390	725	1,390	0
1ST	8+3/4	7	23	0	7,492	795	7,492	0
1ST LINER	6	4+1/2	11.6	6742	11,383	285	11,383	6,742

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments Distance to nearest well permitted/completed in the same formation was calculated from the SHL of the Randall Creek 8-22H to the BHL of the proposed Randall Creek 12-21H.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Nanette Lupcho

Title: Regulatory Assistant Date: 6/9/2011 Email: nanette_lupcho@eogresources.

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

API NUMBER

05

Permit Number: _____ Expiration Date: _____

CONDITIONS OF APPROVAL, IF ANY: _____

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Attachment Check List

Att Doc Num	Name
400173272	FORM 2 SUBMITTED
400173283	WELL LOCATION PLAT
400173284	TOPO MAP
400173303	DRILLING PLAN
400173304	DEVIATED DRILLING PLAN
400173359	LEGAL/LEASE DESCRIPTION
400174372	PLAT

Total Attach: 7 Files

General Comments

User Group	Comment	Comment Date

Total: 0 comment(s)

BMP

Type	Comment

Total: 0 comment(s)