



FIELD TICKET & TREATMENT REPORT CEMENT

TICKET NUMBER 28006
LOCATION Oakley Ks
FOREMAN Walt Dinkel

Colorado

DATE	CUSTOMER #	WELL NAME & NUMBER		SECTION	TOWNSHIP	RANGE	COUNTY	
5-3-11	5659	Jettie 1-34		34	18 ^S	45 ^W	Kiowa	
CUSTOMER Mull Dng. Co., Inc.				Brandon Culo 1W 1N 6E 9	TRUCK #	DRIVER	TRUCK #	DRIVER
MAILING ADDRESS					456-T118	Chad Smith		
					566	Cory Daniels		
CITY		STATE	ZIP CODE					

JOB TYPE	Surface-O	HOLE SIZE	12 1/4	HOLE DEPTH	347'	CASING SIZE & WEIGHT	8 5/8" - 24#
CASING DEPTH	347	DRILL PIPE		TUBING		OTHER	
SLURRY WEIGHT	1.5.2	SLURRY VOL		WATER gal/ek		CEMENT LEFT In CASING	20'
DISPLACEMENT	20 3/4	DISPLACEMENT PSI		MIX PSI		RATE	6 Bpm

REMARKS: Safety Meeting, rig up to Circ
Mix 265 s/s cone, 3% sec - 2% Cal, release Plug
Displace 20 3/4 BBL H₂O
Shut in

Cement Rd Cur.

Approx 5 BBL to Pit

Thank You
Walt & crew

[illegible]

AUTHORIZATION

TITLE

DATE _____

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.


CONSOLIDATED
 Oil Well Services, LLC

 PO Box 884, Chanute, KS 66720
 620-431-8210 or 800-467-8875

FIELD TICKET & TREATMENT REPORT
CEMENT
TICKET NUMBER **28074**LOCATION **Oakley**FOREMAN **Tracy***Wally & crew*

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
5-15-11	5659	Jettie 1-34	34	18S	45W	RIOWA
CUSTOMER Mull Drilling			TRUCK # DRIVER TRUCK # DRIVER			
MAILING ADDRESS			4564729 CHAS			
CITY STATE ZIP CODE			440 CORY D			

 JOB TYPE **Prod Csg** HOLE SIZE **2 7/8** HOLE DEPTH **5911** CASING SIZE & WEIGHT **5 1/2" 14#**
 CASING DEPTH **4898** DRILL PIPE TUBING OTHER
 SLURRY WEIGHT **138** SLURRY VOL **1.5** WATER gal/sk **6.9** CEMENT LEFT IN CASING **28'**
 DISPLACEMENT **119 bbl** DISPLACEMENT PSI **900** MIX PSI RATE

 REMARKS: *Safety meeting, ran flow equip, combinations 2-7, 19, 20, 21, 64, 65, 34000 on 2-6-2. Postcure on 2-6-3 rig up, circulate pump flow check flush, move 15 sks, RH 10 M.H. 230 SKS OWC in casing, cleared pump line, dropped plug, displaced 120 1/2 bbl H2O. Plug landed at 1600 PSI washed up, rigged down, left location.*
*Thanks
Wally & crew*

ACCOUNT CODE	QUANTITY or UNIT'S	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401C	1	PUMP CHARGE	2850	2850.00
5406	100	MILEAGE	5.00	500.00
1126	250 1000 SKS	OWC 250 SKS	21.48	5370.00
110A	12.50*	Kalseal	.53	662.50
1135	59*	CEL 115	9.45	557.55
1102	240*	Calcium Chloride	.844	201.60
1111A	200*	Sodium Metasilicate	2.26	452.00
4203	1	5 1/2" Guide Shoe	193.00	193.00
4228B	1	5 1/2" AFU insert	206.00	206.00
4130	4	5 1/2" centralizers	58.00	232.00
4136	8	5 1/2" turboliners	72.00	576.00
4104	2	5 1/2" baskets	226.00	452.00
4285	1	5 1/2" Postcure	2075.00	2075.00
4406	1	5 1/2" rubber Plug	88.00	88.00
5407A	11.75	Ton mileage delivery	15.50	182.60
		<i>241413</i>		16222.15
		<i>20015%</i>		3440.83
				13831.33
		7.8%	SALES TAX	733.66
			ESTIMATED TOTAL	14564.98

Ravin 3737

AUTHORIZATION

Tracy Ahern

TITLE

Lead Foreman

DATE

5-16-11

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.



PO Box 884, Chanute, KS 66720
820-431-8210 or 800-467-8876

FIELD TICKET & TREATMENT REPORT

TICKET NUMBER 28016

LOCATION Oakley, KS

FOREMAN Kelly Gable
PORT Walt Dinkel

DATE		CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY	
5-19-11		5659	Jettie 1-34				Kiowa	
CUSTOMER MAILING ADDRESS Mall Dels Co				Brandon NW 1N 4E	TRUCK #	DRIVER	TRUCK #	DRIVER
					399	Tim Wobham		
					528-T127	Miles Shaw		
					566	Damon Miller		
CITY		STATE	ZIP CODE					
JOB TYPE Port Cellar		HOLE SIZE	HOLE DEPTH					
CASING DEPTH								

JOB TYPE <u>Port Collar</u>	HOLE SIZE _____	HOLE DEPTH _____	CASING SIZE & WEIGHT _____
CASING DEPTH _____	DRILL PIPE _____	TUBING <u>2 7/8 - 2290'</u>	OTHER _____
SLURRY WEIGHT <u>12.5-14.8</u>	SLURRY VOL _____	WATER gal/sk _____	CEMENT LEFT in CASING _____
DISPLACEMENT <u>13 BBL</u>	DISPLACEMENT PSI _____	MIX PSI <u>500#</u>	RATE <u>5 BPM</u>
REMARKS: <u>Safety Meeting - TWT</u>			

REMARKS: Safety Meeting, Test casing to 1000#, released Pressure
open tool and Pump into 2 4 BPM 2 500#
mixed 380 SKS 60/40, 85/15, 1/4" Flashed. Tail in W/ 50 SKS on
Displace 12 BBL H₂O, Shut Tool and Test to 1000# Hold
ran 5 Jts, circ. casing clean

Thank You
Kelly + crew

[illegible]

Revin 3737

AUTHORIZATION

TITLE

DATE _____

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.