

FORM  
2  
Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission  
1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400165467

Plugging Bond Surety

20040071

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_  
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☒

Refiling ☒  
Sidetrack ☐

3. Name of Operator: ANTERO RESOURCES PICEANCE CORPORATION 4. COGCC Operator Number: 10079

5. Address: 1625 17TH ST STE 300  
City: DENVER State: CO Zip: 80202

6. Contact Name: Hannah Knopping Phone: (303)357-6412 Fax: (303)357-7315  
Email: hknopping@anteroresources.com

7. Well Name: Robinson Well Number: C3

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 8354

WELL LOCATION INFORMATION

10. QtrQtr: SENE Sec: 17 Twp: 6S Rng: 92W Meridian: 6  
Latitude: 39.527264 Longitude: -107.681836

Footage at Surface: 2439 feet FNL/FSL FNL 172 feet FEL/FWL FEL

11. Field Name: Mamm Creek Field Number: 52500

12. Ground Elevation: 5640 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 01/19/2007 PDOP Reading: 1.2 Instrument Operator's Name: Scott E. Aibner

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 371 FNL 361 FEL 371 FNL 361 FEL 371 FNL 361 FEL 371  
Sec: 17 Twp: 6S Rng: 92W Sec: 17 Twp: 6S Rng: 92W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 1030 ft

18. Distance to nearest property line: 170 ft 19. Distance to nearest well permitted/completed in the same formation: 430 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Iles	ILES	191-25	320	N/2
Williams Fork	WMFK	191-24	320	N/2

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: \_\_\_\_\_

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No: ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
T6S, R92W-Section 17: NWNE, Portions of the NENE, Section 16: N/2NWNW (see map previously submitted, Plat #4)

25. Distance to Nearest Mineral Lease Line: \_\_\_\_\_ 371 ft \_\_\_\_\_ 26. Total Acres in Lease: \_\_\_\_\_ 103 \_\_\_\_\_

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☐ Land Farming ☐ Land Spreading ☒ Disposal Facility Other: Onsite if app(see comments)

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	24	16	55#	0	60	177	60	0
SURF	12+1/4	8+5/8	24/32#	0	1,000	416	1,000	0
1ST	7+7/8	4+1/2	11.6#	0	8,354	356	8,354	

32. BOP Equipment Type: ☐ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments I certify that conditions in the original permit are the same except SHL change, BHL change, new TD, new lease information and updated casing program. This Refile Form 2 does not require a Form 2A because the pad has been constructed, a closed loop system is being used so no pits need to be constructed, the refilled well will not require any expansion / additional surface disturbance of the pad. The location is not in a wildlife restricted surface occupancy area (RSO); consultation with CDOW is not required and the location does not require a variance from any of the rules listed in Rule 306.d.(1).(A).(ii).; consultation with CDPHE is not required. #31 Mud Disposal: Antero will bury onsite if disposal meets Table 910 and if there is a provision in SUA which allows for such operation. TOP OF CEMENT OF 1ST STRING/PRODUCTION CASING WILL BE >500 FEET ABOVE TOP OF GAS.

34. Location ID: \_\_\_\_\_ 335546 \_\_\_\_\_

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☐ Yes ☒ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Hannah Knopping

Title: Permit Representative Date: 5/16/2011 Email: hknopping@anteroresources.co

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 6/17/2011

**API NUMBER**

05 045 17105 00

Permit Number: \_\_\_\_\_ Expiration Date: 6/16/2013

**CONDITIONS OF APPROVAL, IF ANY:**

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1.) THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1 MILE IS 300 FEET DEEP.

2.) PRODUCTION CASING CEMENT TOP VERIFICATION BY CBL REQUIRED.

**Attachment Check List**

Att Doc Num	Name
400165467	FORM 2 SUBMITTED
400165470	SURFACE AGRMT/SURETY
400165471	30 DAY NOTICE LETTER
400165472	WELL LOCATION PLAT
400165473	DEVIATED DRILLING PLAN

Total Attach: 5 Files

**General Comments**

User Group	Comment	Comment Date

Total: 0 comment(s)

**BMP**

Type	Comment

Total: 0 comment(s)