

FORM
2

Rev
12/05

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400171310

Plugging Bond Surety

20100108

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER ☐ PILOT ☐
SINGLE ZONE ☐ MULTIPLE ☐ COMMINGLE ☐

Refiling ☐

Sidetrack ☐

3. Name of Operator: CARRIZO OIL & GAS INC

4. COGCC Operator Number: 10338

5. Address: 1000 LOUISIANA STREET #1500

City: HOUSTON State: TX Zip: 77002

6. Contact Name: Fabrianna Venaducci Phone: (303)279-0789 Fax: (303)279-1124

Email: fabrianna@jameskaro.com

7. Well Name: Slick Rock Well Number: 18-44-7-60

8. Unit Name (if appl): Unit Number:

9. Proposed Total Measured Depth: 6999

WELL LOCATION INFORMATION

10. QtrQtr: SESE Sec: 18 Twp: 7N Rng: 60W Meridian: 6

Latitude: 40.568590 Longitude: -104.130600

Footage at Surface: 245 feet FNL/FSL 965 feet FEL/FWL FEL

11. Field Name: wildcat Field Number: 99999

12. Ground Elevation: 4922.5 13. County: WELD

14. GPS Data:

Date of Measurement: 04/14/2011 PDOP Reading: 1.8 Instrument Operator's Name: L. Kelley Stevenson

15. If well is ☐ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL

Sec: Twp: Rng: Sec: Twp: Rng:

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 223 ft

18. Distance to nearest property line: 245 ft 19. Distance to nearest well permitted/completed in the same formation: 5205 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
D Sand	DSND			
Niobrara	NBRR			

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #:

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: 20100170

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☒ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

7N, 60W, Sec. 18: ALL

25. Distance to Nearest Mineral Lease Line: 245 ft

26. Total Acres in Lease: 640

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☐ Offsite ☒ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☒ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	9+5/8	36	0	1,400	534	1,400	0

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments THIS FORM 2 IS SUBMITTED FOR A PILOT HOLE IN CONJUNCTION WITH FORM 2 (HORIZONTAL - DOCUMENT NUMBER 400171328) AND FORM 2A (DOCUMENT NUMBER 400171337), and attachments submitted with said forms are applicable to this pilot hole. Application for a drilling and spacing unit has been made and is on the June 27 and 28, 2011 docket for approval. Well Location Certificate/Plat reflects pad elevation. Ground elevation and pad elevation are the same. Distance to the nearest well permitted/completed in the same formation is for the proposed Slick Rock 19-44-7-60, pilot hole to pilot hole. Pilot hole will be plugged back at TD to 5575' with 811 sacks of cement; hole size is 8.75".

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Fabrianna Venaducci

Title: Contract Landman

Date: _____

Email: fabrianna@jameskaro.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

API NUMBER

05

Permit Number: _____ Expiration Date: _____

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Attachment Check List

Att Doc Num	Name
400172006	TOPO MAP
400173381	WELL LOCATION PLAT

Total Attach: 2 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

BMP

<u>Type</u>	<u>Comment</u>
Construction	<p>Operator has designed the well pad with insloping and a storm water control ditch to prevent storm water run-on/runoff and the release of fluids from the location. See attached Construction Layout Drawing.</p> <p>The location will be fenced and the fenced area will include the Fresh Water Storage Pit.</p> <p>The COGCC to be notified 48 hours prior to construction of the Fresh Water Storage Pit.</p>
Drilling/Completion Operations	<p>Operator will ensure 110 percent secondary containment for any volume of fluids contained at the well site during drilling and completion. Operator will implement best management practices to contain any unintentional release of fluids.</p> <p>Fresh water for the Fresh Water Storage Pit comes from water provider; water sources permitted for consumable industrial use.</p> <p>Operator shall not allow any fluids to flow back to the Fresh Water Storage Pit.</p> <p>Fresh Water Storage Pit shall contain fresh water only and signage prohibiting the use of the pit for any fluid that does not come from municipal, irrigation or surface water source.</p>

Total: 2 comment(s)