

21. Mineral Ownership: Fee State Federal Indian Lease #: _____

22. Surface Ownership: Fee State Federal Indian

23. Is the Surface Owner also the Mineral Owner? Yes No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? Yes No

23b. If 23 is No: Surface Owners Agreement Attached or \$25,000 Blanket Surface Bond \$2,000 Surface Bond \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
 Lot 4, NW/4 & E/2, Sec. 6, T8N-R43W; W/2, Sec. 30, T8N-R43W

25. Distance to Nearest Mineral Lease Line: 258 ft 26. Total Acres in Lease: 855

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? Yes No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? Yes No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? Yes No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? Yes No

31. Mud disposal: Offsite Onsite **If 28, 29, or 30 are "Yes" a pit permit may be required.**

Method: Land Farming Land Spreading Disposal Facility Other: Evap & Burial

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	9+7/8	7+0/0	17#	12	450	180	450	0
1ST	6+1/4	4+1/2	10.5#	12	3,000	80	3,000	1,600

32. BOP Equipment Type: Annular Preventer Double Ram Rotating Head None

33. Comments No conductor casing will be used. The perforated interval is estimated to be shallower than 2500 ft.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan? Yes No

36. Is this application part of submitted Oil and Gas Location Assessment? Yes No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Janice Aldstadt

Title: Landman Date: 5/9/2011 Email: jaldstadt@blackravenenergy.co

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 6/24/2011

API NUMBER
 05 095 06316 00 Permit Number: _____ Expiration Date: 6/23/2013

CONDITIONS OF APPROVAL, IF ANY: _____

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

The perforated interval or completed interval must be shallower than 2500 feet in vertical depth without an approved exception location.

- 1) Provide 24 hour notice of MIRU to Bo Brown via e-mail at bo.brown@state.co.us.
- 2) Provide cement coverage from TD to a minimum of 200' above Niobrara. Verify coverage with cement bond log.
- 3) If dry hole, set 40 sks cement 50' above Niobrara top, 50 sks cement from 50' below to 50' above surface casing shoe, 10 sks cement top of surface casing, cut 4' below GL, weld on plate, 5 sks cement in rat hole & 5 sks cement in mouse hole.

Attachment Check List

Att Doc Num	Name
2566865	SURFACE CASING CHECK
400154868	FORM 2 SUBMITTED
400154885	WELL LOCATION PLAT
400154887	TOPO MAP

Total Attach: 4 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)