


FORM 2 Rev 12/05	State of Colorado Oil and Gas Conservation Commission 1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109		<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 25%;">DE</td> <td style="width: 25%;">ET</td> <td style="width: 25%;">OE</td> <td style="width: 25%;">ES</td> </tr> </table>	DE	ET	OE	ES
DE	ET	OE	ES				
APPLICATION FOR PERMIT TO:			Document Number: 400163480 Plugging Bond Surety 20070004				
1. <input checked="" type="checkbox"/> Drill, <input type="checkbox"/> Deepen, <input type="checkbox"/> Re-enter, <input type="checkbox"/> Recomplete and Operate							
2. TYPE OF WELL OIL <input checked="" type="checkbox"/> GAS <input type="checkbox"/> COALBED <input type="checkbox"/> OTHER _____ SINGLE ZONE <input checked="" type="checkbox"/> MULTIPLE ZONE <input type="checkbox"/> COMMINGLE ZONE <input type="checkbox"/>		Refiling <input type="checkbox"/> Sidetrack <input type="checkbox"/>					
3. Name of Operator: <u>BONANZA CREEK ENERGY OPERATING COMPANY LLC</u>		4. COGCC Operator Number: <u>8960</u>					
5. Address: <u>P O BOX 21974</u> City: <u>BAKERSFIELD</u> State: <u>CA</u> Zip: <u>93390</u>							
6. Contact Name: <u>Keith Caplan</u> Phone: <u>(720)440-6112</u> Fax: <u>(720)279-2331</u> Email: <u>KCaplan@bonanzacrk.com</u>							
7. Well Name: <u>Antelope</u>		Well Number: <u>14-20</u>					
8. Unit Name (if appl): _____		Unit Number: _____					
9. Proposed Total Measured Depth: <u>6800</u>							
WELL LOCATION INFORMATION							
10. QtrQtr: <u>SWSW</u> Sec: <u>20</u> Twp: <u>5N</u> Rng: <u>62W</u> Meridian: <u>6</u> Latitude: <u>40.379950</u> Longitude: <u>-104.355000</u>							
Footage at Surface: <u>772</u> feet FNL/FSL <u>FSL</u> 470 feet FEL/FWL <u>FWL</u>							
11. Field Name: <u>Wattenberg</u>		Field Number: <u>90750</u>					
12. Ground Elevation: <u>4558</u>		13. County: <u>WELD</u>					
14. GPS Data: Date of Measurement: <u>05/02/2011</u> PDOP Reading: <u>2.6</u> Instrument Operator's Name: <u>Dan Griggs</u>							
15. If well is <input type="checkbox"/> Directional <input type="checkbox"/> Horizontal (highly deviated) submit deviated drilling plan. Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL _____ Sec: _____ Twp: _____ Rng: _____ Sec: _____ Twp: _____ Rng: _____							
16. Is location in a high density area? (Rule 603b)? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No							
17. Distance to the nearest building, public road, above ground utility or railroad: <u>182 ft</u>							
18. Distance to nearest property line: <u>470 ft</u> 19. Distance to nearest well permitted/completed in the same formation: <u>1115 ft</u>							
LEASE, SPACING AND POOLING INFORMATION							
Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)			
Niobrara-Codell	NB-CD		40	SWSW			

IMPORTANT: SOME DATA FIELDS HAVE BEEN MODIFIED.

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: 20070001

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☒ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

T4N-R62W: SEC. 3: NW/4 SEC. 5: ALL SEC. 7: SW/4 NW/4, W/2 SW/4 SEC. 17: NE/4, N/2 NW/4 SEC. 18: N/2 N/2 T4N-R63W: SEC. 1: LOT 1 AND 2, S/2 N/2, S/2 SEC. 2: NE/4, NE/4 SE/4, N/2 NW/4 SEC. 12: NE/4, E/2 NW/4, E/2 SE/4 T5N-R62W: SEC. 3: LOT 2, SW/4 NE/4, W/2 SE/4 SEC. 15: W/2 E/2, W/2 SEC. 17: ALL SEC. 18: LOT 1-4, E/2 W/2, SE/4 SEC. 19: ALL (EXCEPT NW/4 NW/4) SEC. 20: W/2 SEC. 21: ALL SEC. 29: ALL SEC. 31: ALL SEC. 33: N/2 T5N-R63W: SEC. 24 W/2 SEC. 34: SE/4 NE/4, SE/4 SEC. 35: S/2 SEC. 36: SW/4 SW/4

25. Distance to Nearest Mineral Lease Line: 2109 ft 26. Total Acres in Lease: 8437

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: _____

If 28, 29, or 30 are "Yes" a pit permit may be required.

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	8+5/8	24	0	420	273	420	0
1ST	7+7/8	4+1/2	11.6	0	6,800	200	6,800	5,950

32. BOP Equipment Type: ☒ Annular Preventer ☐ Double Ram ☐ Rotating Head ☐ None

33. Comments Conductor casing will not be used on this well.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Keith Caplan

Title: Sr. Operations Tech Date: 5/23/2011 Email: KCaplan@bonanzacrk.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Nesline Director of COGCC Date: 6/24/2011

API NUMBER

05 123 33715 00

Permit Number: _____ Expiration Date: 6/23/2013

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Derrick height (ground to crown) cannot exceed 121 feet due to close proximity to building, power line or public road.

- 1) Provide 24 hour notice of MIRU to Bo Brown at 970-397-4124 or e-mail at bo.brown@state.co.us.
- 2) Provide cement coverage from TD to a minimum of 200' above Niobrara. Verify coverage with cement bond log.

Attachment Check List

Att Doc Num	Name
2567577	SURFACE CASING CHECK
400163480	FORM 2 SUBMITTED
400167753	PLAT

Total Attach: 3 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)