

FORM
2
Rev
12/05

State of Colorado
Oil and Gas Conservation Commission
1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400167434

Plugging Bond Surety

20010124

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☐

Refiling ☐
Sidetrack ☐

3. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP 4. COGCC Operator Number: 47120
5. Address: P O BOX 173779
City: DENVER State: CO Zip: 80217-3779
6. Contact Name: REBECCA HEIM Phone: (720)929-6361 Fax: (720)929-7361
Email: rebecca.heim@anadarko.com
7. Well Name: HOWARD Well Number: 26-32
8. Unit Name (if appl): _____ Unit Number: _____
9. Proposed Total Measured Depth: 8795

WELL LOCATION INFORMATION

10. QtrQtr: SWNE Sec: 32 Twp: 1N Rng: 67W Meridian: 6
Latitude: 40.010453 Longitude: -104.910552

Footage at Surface: 1597 feet FNL/FSL FNL 1595 feet FEL/FWL FEL

11. Field Name: WATTENBERG Field Number: 90750
12. Ground Elevation: 5047 13. County: WELD

14. GPS Data:

Date of Measurement: 03/17/2011 PDOP Reading: 2.2 Instrument Operator's Name: OWEN McKEE

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 50 FNL 50 FEL 50 FEL 50 Bottom Hole: FNL/FSL 50 FNL 50 FEL 50 FEL 50
Sec: 32 Twp: 1N Rng: 67W Sec: 32 Twp: 1N Rng: 67W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 1017 ft

18. Distance to nearest property line: 878 ft 19. Distance to nearest well permitted/completed in the same formation: 1714 ft

20. **LEASE, SPACING AND POOLING INFORMATION**

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
J Sand	JSND	232	160	GWA
Niobrara Codell	NB-CD	407	160	GWA

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No: ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
PLEASE SEE ATTACHED OGL.

25. Distance to Nearest Mineral Lease Line: _____ 50 ft 26. Total Acres in Lease: _____ 420

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	8+5/8	24	0	1,150	805	1,150	
1ST	7+7/8	4+1/2	11.6	0	8,795	200	8,795	

32. BOP Equipment Type: ☒ Annular Preventer ☐ Double Ram ☒ Rotating Head ☐ None

33. Comments No conductor casing will be used. Unit Configuration: NB-CD & JSND 32: NE/4NE/4; 33: NW/4NW/4; 28: SW/4SW/4; 29: SE/4SE/4

34. Location ID: _____ 317871

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: REBECCA HEIM

Title: REGULATORY ANALYST II Date: 5/20/2011 Email: DJREGULATORY@ANADARK

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 6/24/2011

API NUMBER

05 123 33721 00

Permit Number: _____ Expiration Date: 6/23/2013

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- 1) Provide 24 hour notice of MIRU to Jim Precup at 303-469-1902 or e-mail at james.precup@state.co.us
- 2) Comply with Rule 317.i and provide cement coverage from TD to a minimum of 200' above Niobrara and from 200' below Sussex to 200' above Sussex. Verify coverage with cement bond log.
- 3) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

Attachment Check List

Att Doc Num	Name
400167434	FORM 2 SUBMITTED
400167440	30 DAY NOTICE LETTER
400167441	DEVIATED DRILLING PLAN
400167442	PLAT
400167443	PROPOSED SPACING UNIT
400167444	TOPO MAP
400167445	OIL & GAS LEASE
400167447	SURFACE AGRMT/SURETY

Total Attach: 8 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)