


FORM 2 Rev 12/05	State of Colorado Oil and Gas Conservation Commission 1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109		<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 25%;">DE</td> <td style="width: 25%;">ET</td> <td style="width: 25%;">OE</td> <td style="width: 25%;">ES</td> </tr> </table>	DE	ET	OE	ES
DE	ET	OE	ES				
APPLICATION FOR PERMIT TO:			Document Number: <div style="text-align: center;">400166841</div> Plugging Bond Surety <div style="text-align: center;">20070004</div>				
1. <input checked="" type="checkbox"/> Drill, <input type="checkbox"/> Deepen, <input type="checkbox"/> Re-enter, <input type="checkbox"/> Recomplete and Operate							
2. TYPE OF WELL OIL <input checked="" type="checkbox"/> GAS <input type="checkbox"/> COALBED <input type="checkbox"/> OTHER _____ SINGLE ZONE <input checked="" type="checkbox"/> MULTIPLE ZONE <input type="checkbox"/> COMMINGLE ZONE <input type="checkbox"/>		Refiling <input type="checkbox"/> Sidetrack <input type="checkbox"/>					
3. Name of Operator: <u>BONANZA CREEK ENERGY OPERATING COMPANY LLC</u>		4. COGCC Operator Number: <u>8960</u>					
5. Address: <u>P O BOX 21974</u> City: <u>BAKERSFIELD</u> State: <u>CA</u> Zip: <u>93390</u>							
6. Contact Name: <u>Keith Caplan</u> Phone: <u>(720)440-6112</u> Fax: <u>(720)279-2331</u> Email: <u>KCaplan@bonanzacrk.com</u>							
7. Well Name: <u>Antelope</u>		Well Number: <u>42-17</u>					
8. Unit Name (if appl): _____		Unit Number: _____					
9. Proposed Total Measured Depth: <u>7000</u>							
WELL LOCATION INFORMATION							
10. QtrQtr: <u>NENE</u> Sec: <u>17</u> Twp: <u>5N</u> Rng: <u>62W</u> Meridian: <u>6</u> Latitude: <u>40.404910</u> Longitude: <u>-104.340050</u>							
Footage at Surface: <u>690</u> feet <u>FNL</u> <u>660</u> feet <u>FEL</u>							
11. Field Name: <u>Wattenberg</u>		Field Number: <u>90750</u>					
12. Ground Elevation: <u>4708</u>		13. County: <u>WELD</u>					
14. GPS Data: Date of Measurement: <u>05/23/2011</u> PDOP Reading: <u>2.1</u> Instrument Operator's Name: <u>Dan Griggs</u>							
15. If well is <input checked="" type="checkbox"/> Directional <input type="checkbox"/> Horizontal (highly deviated) submit deviated drilling plan. Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL <div style="display: flex; justify-content: space-around;"> <div> <u>1320</u> <u>FNL</u> <u>660</u> <u>FEL</u> </div> <div> <u>1320</u> <u>FNL</u> <u>660</u> <u>FEL</u> </div> </div> <div style="display: flex; justify-content: space-around;"> <div> Sec: <u>17</u> Twp: <u>5N</u> Rng: <u>62W</u> </div> <div> Sec: <u>17</u> Twp: <u>5N</u> Rng: <u>62W</u> </div> </div>							
16. Is location in a high density area? (Rule 603b)? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No							
17. Distance to the nearest building, public road, above ground utility or railroad: <u>556 ft</u>							
18. Distance to nearest property line: <u>660 ft</u> 19. Distance to nearest well permitted/completed in the same formation: <u>2540 ft</u>							
LEASE, SPACING AND POOLING INFORMATION							
Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)			
Niobrara-Codell	NB-CD		40	SENE			

IMPORTANT: SOME DATA FIELDS HAVE BEEN MODIFIED.

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: 20070001

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☒ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
Please see attached.

25. Distance to Nearest Mineral Lease Line: 660 ft 26. Total Acres in Lease: 9046

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☒ Offsite ☐ Onsite **If 28, 29, or 30 are "Yes" a pit permit may be required.**

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	8+5/8	24	0	500	325	500	0
1ST	7+7/8	4+1/2	11.6	0	7,000	200	7,000	6,150

32. BOP Equipment Type: ☒ Annular Preventer ☐ Double Ram ☐ Rotating Head ☐ None

33. Comments Conductor casing will not be used on this well.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Keith Caplan

Title: Sr. Operations Tech Date: 5/20/2011 Email: KCaplan@bonanzacrk.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 6/24/2011

API NUMBER

05 123 33726 00

Permit Number: _____ Expiration Date: 6/23/2013

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- 1) Provide 24 hour notice of MIRU to Bo Brown at 970-397-4124 or e-mail at bo.brown@state.co.us.
- 2) Set at least 500' of surface casing, cement to surface.
- 3) Provide cement coverage from TD to a minimum of 200' above Niobrara. Verify coverage with cement bond log.
- 4) Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.
- 5) If dry hole, Set 60 sks cement from 50' below D Sand base to 100' above D Sand top. Set 40 sks cement 50' above Niobrara top, 50 sks cement from 50' below to 50' above surface casing shoe, 15 sks cement top of surface casing, cut 4' below GL, weld on plate, 5 sks cement in rat hole & 5 sks cement in mouse hole.

Attachment Check List

Att Doc Num	Name
2530685	WELL LOCATION PLAT
2530686	DEVIATED DRILLING PLAN
400166841	FORM 2 SUBMITTED
400167143	LEGAL/LEASE DESCRIPTION

Total Attach: 4 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Well moved.	5/27/2011 2:47:43 PM
Permit	On hold The pad was staked off-center in the 400' Window and we have subsequently decided to move the pad to the center of the NE/4 NE/4 Window in Section 17-5N-62W due to Formation Spacing associated with the well to be drilled vertically from that pad. The move will be approximately 180 ft, +/- 20 ft.	5/26/2011 4:36:48 PM

Total: 2 comment(s)

BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)