

FORM
2

Rev
12/05

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400178072

Plugging Bond Surety

20100108

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER Horizontal
SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refiling ☐

Sidetrack ☐

3. Name of Operator: CARRIZO OIL & GAS INC

4. COGCC Operator Number: 10338

5. Address: 1000 LOUISIANA STREET #1500

City: HOUSTON State: TX Zip: 77002

6. Contact Name: Terry Hoffman Phone: (720)542-8287 Fax: (720)542-9213

Email: terry@rockymountainpermitting.com

7. Well Name: Shull Well Number: 35-11-9-60

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 10920

WELL LOCATION INFORMATION

10. QtrQtr: NWNW Sec: 35 Twp: 9N Rng: 60W Meridian: 6

Latitude: 40.713206 Longitude: -104.067811

Footage at Surface: 245 feet FNL/FSL 245 feet FEL/FWL FWL

11. Field Name: Wildcat Field Number: 99999

12. Ground Elevation: 4942 13. County: WELD

14. GPS Data:

Date of Measurement: 05/26/2011 PDOP Reading: 1.8 Instrument Operator's Name: L.S.

15. If well is ☐ Directional ☒ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 650 FNL 650 FWL 650 FSL 1991 FWL FWL
Sec: 35 Twp: 9N Rng: 60W Sec: 35 Twp: 9N Rng: 60W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 218 ft

18. Distance to nearest property line: 245 ft 19. Distance to nearest well permitted/completed in the same formation: 2356 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Niobrara	NBRR	535.3	640	All

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

See two attached leases covering this well, too much information to type.

25. Distance to Nearest Mineral Lease Line: 649 ft

26. Total Acres in Lease: 7165

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☐ Offsite ☒ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Landfarm Burial or

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	9+5/8	36	0	1,400	534	1,400	0
1ST	8+3/4	7	23	0	6,599	627	6,599	1,400
2ND	6+1/8	4+1/2	11.6	0	10,920	373	10,920	5,599

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments No surface casing will be set. All footages 5280' are 1 mile or greater.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Terry L. Hoffman

Title: Permit Agent

Date: _____

Email: terry@rockymountainpermitting.

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

API NUMBER

05

Permit Number: _____ Expiration Date: _____

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Attachment Check List

Att Doc Num	Name
400178156	PLAT
400178157	DEVIATED DRILLING PLAN
400178782	OIL & GAS LEASE
400178783	OIL & GAS LEASE

Total Attach: 4 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

BMP

<u>Type</u>	<u>Comment</u>
Construction	<p>Operator will ensure 110 percent secondary containment for any volume of fluids contained at the well site during drilling and completion.</p> <p>Operator will implement best management practices to contain any unintentional release of fluids.</p> <p>Operator has designed the well pad with insloping and a storm water control ditch to prevent storm water run-on/runoff and the release of fluids from the location. See attached Construction Layout Drawing.</p> <p>Fresh water for the Fresh Water Storage Pit comes from water provider; water sources permitted for consumable industrial use.</p> <p>Operator shall not allow any fluids to flow back to the Fresh Water Storage Pit.</p> <p>Fresh Water Storage Pit shall contain fresh water only and signage prohibiting the use of the pit for any fluid that does not come from municipal, irrigation or surface water source.</p> <p>The location will be fenced and the fenced area will include the Fresh Water Storage Pit.</p> <p>The COGCC to be notified 48 hours prior to construction of the Fresh Water Storage Pit.</p>

Total: 1 comment(s)