

FORM  
2Rev  
12/05

## State of Colorado

## Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



|    |    |    |    |
|----|----|----|----|
| DE | ET | OE | ES |
|----|----|----|----|

## APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

## 2. TYPE OF WELL

 OIL ☒ GAS ☐ COALBED ☐ OTHER \_\_\_\_\_  
 SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐
Refiling ☐Sidetrack ☐

Document Number:

400161661

Plugging Bond Surety

20030009

3. Name of Operator: NOBLE ENERGY INC

4. COGCC Operator Number: 100322

5. Address: 1625 BROADWAY STE 2200

City: DENVER State: CO Zip: 80202

6. Contact Name: SUSAN MILLER Phone: (303)228-4246 Fax: (303)228-4286

Email: smiller@nobleenergyinc.com

7. Well Name: PATRIOT Well Number: B16-69HN

8. Unit Name (if appl): Unit Number:

9. Proposed Total Measured Depth: 11086

## WELL LOCATION INFORMATION

10. QtrQtr: SWSW Sec: 9 Twp: 5N Rng: 64W Meridian: 6

Latitude: 40.408030 Longitude: -104.563140

 Footage at Surface: 537 feet FNL/FSL FSL 380 feet FEL/FWL  
 FSL FWL

11. Field Name: Kersey Field Number: 44600

12. Ground Elevation: 4603 13. County: WELD

## 14. GPS Data:

Date of Measurement: 04/15/2011 PDOP Reading: 2.2 Instrument Operator's Name: Brian Brinkman

15. If well is ☐ Directional ☒ Horizontal (highly deviated) submit deviated drilling plan.
 Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL  
 82 FSL 692 FWL 75 FSL 535 FEL  
 Sec: 9 Twp: 5N Rng: 64W Sec: 9 Twp: 5N Rng: 64W
16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 246 ft

18. Distance to nearest property line: 250 ft 19. Distance to nearest well permitted/completed in the same formation: 676 ft

## 20. LEASE, SPACING AND POOLING INFORMATION

| Objective Formation(s) | Formation Code | Spacing Order Number(s) | Unit Acreage Assigned to Well | Unit Configuration (N/2, SE/4, etc.) |
|------------------------|----------------|-------------------------|-------------------------------|--------------------------------------|
| Niobrara               | NBRR           | 407-87                  | 320                           | See Comments                         |

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#:23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

Please see attached Mineral Lease Map. Noble Energy Inc certifies that the leases shall be committed to the unit.

25. Distance to Nearest Mineral Lease Line: 535 ft

26. Total Acres in Lease: 6773

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☒ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: CLOSED LOOP

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

| Casing Type | Size of Hole | Size of Casing | Wt/Ft | Csg/Liner Top | Setting Depth | Sacks Cmt | Cmt Btm | Cmt Top |
|-------------|--------------|----------------|-------|---------------|---------------|-----------|---------|---------|
| SURF        | 13+3/4       | 9+5/8          | 36    | 0             | 650           | 409       | 650     | 0       |
| 1ST         | 8+3/4        | 7              | 26    | 0             | 7,049         | 1,036     | 7,049   |         |
| 1ST LINER   | 6+1/8        | 4+1/2          | 11.6  | 6136          | 11,086        |           |         |         |

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments Conductor casing will not be used. First string top of cement will be 200' above the Niobrara formation. The production liner will be hung off inside of the 7" casing. Unit Configuration: Sec 9: S/2S/2, Sec 16: N/2N/2.

34. Location ID: \_\_\_\_\_

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: SUSAN MILLER

Title: Regulatory Analyst II Date: 6/28/2011 Email: smiller@nobleenergyinc.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

API NUMBER

05

Permit Number: \_\_\_\_\_ Expiration Date: \_\_\_\_\_

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

### Attachment Check List

| Att Doc Num | Name                   |
|-------------|------------------------|
| 400161661   | FORM 2 SUBMITTED       |
| 400161704   | 30 DAY NOTICE LETTER   |
| 400161705   | EXCEPTION LOC WAIVERS  |
| 400161711   | EXCEPTION LOC REQUEST  |
| 400165823   | WELL LOCATION PLAT     |
| 400165825   | DEVIATED DRILLING PLAN |
| 400165826   | PROPOSED SPACING UNIT  |
| 400165827   | PROPOSED SPACING UNIT  |
| 400179457   | PROPOSED SPACING UNIT  |
| 400179458   | MINERAL LEASE MAP      |

Total Attach: 10 Files

### General Comments

| <u>User Group</u> | <u>Comment</u> | <u>Comment Date</u> |
|-------------------|----------------|---------------------|
|                   |                |                     |

Total: 0 comment(s)

### BMP

| <u>Type</u>                            | <u>Comment</u>  |
|--|---|
| General Housekeeping                   | General housekeeping will consist of neat and orderly storage of materials and fluids. Wastes will be temporarily stored in sealed containers and regularly collected and disposed of at offsite, suitable facilities. If spills occur, prompt cleanup is required to minimize any commingling of waste materials with stormwater runoff. Routine maintenance will be limited to fueling and lubrication of equipment. Drip pans will be used during routine fueling and maintenance to contain spills or leaks. Any waste product from maintenance will be containerized and transported offsite for disposal or recycling. There will be no major equipment overhauls conducted onsite. Equipment will be transported offsite for major overhauls. Cleanup of trash and discarded materials will be conducted at the end of each work day. Cleanup will consist of patrolling the roadway, access areas, and other work areas to pick up trash, scrap debris, other discarded materials, and any contaminated soil. These materials will be disposed of properly. |
| Storm Water/Erosion Control            | Stormwater management plans (SWMP) are in place to address construction, drilling and operations associated with Oil & Gas development throughout the state of Colorado in accordance with Colorado Department of Public Health and Environment (CDPHE) and General Permit No. COR-039527. BMP's will be constructed around the perimeter of the site prior to, or at the beginning of construction. BMP's used will vary according to the location and will remain in place until the pad reaches final reclamation.   |
| Material Handling and Spill Prevention | Spill Prevention Control and Countermeasures (SPCC) plans are in place to address any possible spill associated with Oil & Gas operations throughout the state of Colorado in accordance with CFR 112.  |

Total: 3 comment(s)