

WELLBORE DIAGRAM
Conquest Oil Company
C8A

NESE, Sec. 29, T11N, R62W
Weld County, CO
05-123-32858

5/20/2011
RO

K.B.= 5196
G.L.= 5176
20

TOPS

Grnhn - 7524'
J Silt - 7796'
J Sand - 7822'

9-5/8", 26# K-55 LT&C CSG Set @ 1241' (12-1/4" O.H.)
Cmt'd w/ 455 sx to Surface

7", 23# N-80 LT&C CSG Set @ 9044' (8-3/4" O.H.)
Cmt'd w/ 1110 sx
TOL @ 8988'
#7 ECP @ 8998'

Lyons - 9000'

L. Satanka- 9204'

#6 ECP @ 9202'
Blank Pipe

Wolfcamp- 9328'

#5 ECP @ 9332'

Amazon - 9428'
Ccl Grove-9505'

#4 ECP @ 9424'

Admire - 9602'
Virgil - 9746'
Missouri - 9990' to

#3 ECP @ 9616'

10200

DesMoines - 10200'

#2 ECP @ 10072'

Atokan - 10386'

#1 ECP @ 10215'

4-1/2" 11.6# P-110 LT&C Slotted LNR (TOL @ 8973', EOL @ 10,552') (6-1/8" OH)

TD= 10,557'

ECP = Estimated Center of Packer Depths have been adjusted to match gamma ray