

FORM
2
Rev
12/05

State of Colorado
Oil and Gas Conservation Commission
1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400173100

Plugging Bond Surety

20000108

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER _____
SINGLE ZONE ☒ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐

Refiling ☐
Sidetrack ☐

3. Name of Operator: ST CROIX OPERATING INC 4. COGCC Operator Number: 81490
5. Address: P O BOX 13799
City: DENVER State: CO Zip: 80201
6. Contact Name: CLAYTON DOKE Phone: (970)669-7411 Fax: (970)669-4077
Email: cdoke@petersonenergy.com
7. Well Name: MONTY NIEBUR Well Number: 1
8. Unit Name (if appl): _____ Unit Number: _____
9. Proposed Total Measured Depth: 4150

WELL LOCATION INFORMATION

10. QtrQtr: NENW Sec: 23 Twp: 2S Rng: 51W Meridian: 6
Latitude: 39.871540 Longitude: -103.060510

Footage at Surface: 660 feet FNL/FSL 1980 feet FEL/FWL
FNL FWL

11. Field Name: WILDCAT Field Number: 99999
12. Ground Elevation: 4579 13. County: WASHINGTON

14. GPS Data:

Date of Measurement: 02/17/2011 PDOP Reading: 1.7 Instrument Operator's Name: RON EDWARDS

15. If well is ☐ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL _____ FEL/FWL _____ Bottom Hole: FNL/FSL _____ FEL/FWL _____
Sec: _____ Twp: _____ Rng: _____ Sec: _____ Twp: _____ Rng: _____

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 3475 ft

18. Distance to nearest property line: 660 ft 19. Distance to nearest well permitted/completed in the same formation: 4 mi

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
J Sand	JSND		40	NENW

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No: ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
TOWNSHIP 2 SOUTH, RANGE 51 WEST, SECTION 23: ALL

25. Distance to Nearest Mineral Lease Line: _____ 660 ft _____ 26. Total Acres in Lease: _____ 640 _____

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

If 28, 29, or 30 are "Yes" a pit permit may be required.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	8+5/8	24	0	500	330	500	0
1ST	7+7/8	4+1/2	11.6	0	4,150	315	4,150	2,790

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments No conductor casing will be run.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: CLAYTON DOKE

Title: CONSULTANT Date: 6/9/2011 Email: cdoke@petersonenergy.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 7/5/2011

API NUMBER

05 121 11009 00

Permit Number: _____ Expiration Date: 7/4/2013

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- 1) Provide 24 hr notice of spud to Colby Horton at 970-467-2517 or e-mail at colby.horton@state.co.us.
- 2) If completed, provide cement coverage from TD to a minimum of 200' above Niobrara. Verify coverage with cement bond log.
- 3) If dry hole, set 60 sks cement from 50' below D Sand base to 100' above D Sand top, 40 sks cement 50' above Niobrara top, 50 sks cement ½ out, ½ in surface casing, 15 sks cement top of surface casing, cut 4' below GL, weld on plate, 5 sks cement in rat hole & 5 sks cement in mouse hole.

Attachment Check List

Att Doc Num	Name
400173100	FORM 2 SUBMITTED
400173109	WELL LOCATION PLAT
400173136	SURFACE AGRMT/SURETY

Total Attach: 3 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Form 1A processed. sf	6/14/2011 1:01:08 PM
Permit	Pushed back to Draft Contact and Signatory agent is not a authorized agent Attachment name changed from Plat to Well Location Plat	6/10/2011 8:48:12 AM

Total: 2 comment(s)

BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)