

**FORM  
5**Rev  
02/08**State of Colorado  
Oil and Gas Conservation Commission**

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400181966

**DRILLING COMPLETION REPORT**

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 47120

4. Contact Name: Cindy Vue

2. Name of Operator: KERR-MCGEE OIL &amp; GAS ONSHORE LP

Phone: (720) 929-6832

3. Address: P O BOX 173779

Fax: (720) 929-7832

City: DENVER State: CO Zip: 80217-

5. API Number 05-123-32141-00

6. County: WELD

7. Well Name: WILDFLOWER

Well Number: 14-27

8. Location: QtrQtr: SESW Section: 27 Township: 2N Range: 68W Meridian: 6

Footage at surface: Distance: 1057 feet Direction: FSL Distance: 1332 feet Direction: FWL

As Drilled Latitude: 40.105183 As Drilled Longitude: -104.994061

GPS Data:

Data of Measurement: 05/03/2011 PDOP Reading: 2.2 GPS Instrument Operator's Name: Renee Doiron

\*\* If directional footage

at Top of Prod. Zone Distance: 512 feet Direction: FSL Distance: 2123 feet Direction: FWL

Sec: 27 Twp: 2N Rng: 68W

at Bottom Hole Distance: 510 feet Direction: FSL Distance: 2136 feet Direction: FWL

Sec: 27 Twp: 2N Rng: 68W

9. Field Name: SPINDLE

10. Field Number: 77900

11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 03/29/2011 13. Date TD: 04/01/2011 14. Date Casing Set or D&amp;A: 04/02/2011

15. Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 8336 TVD 8243 17 Plug Back Total Depth MD 8297 TVD 8224

18. Elevations GR 5008 KB 5022

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

SD-DSN-AC-TR; CBL

20. Casing, Liner and Cement:

**CASING**

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
SURF	12+1/4	8+5/8	24#	0	799	500	0	799	CALC
1ST	7+7/8	4+1/2	11.6#	0	8,326	230	6,720	8,326	CBL

**ADDITIONAL CEMENT**

Cement work date: 04/02/2011

## Details of work:

Method used	String	Cementing tool setting/pref depth	Cement volume	Cement top	Cement bottom
DV TOOL	1ST	6,112	641	110	6,112

## 21. Formation log intervals and test zones:

**FORMATION LOG INTERVALS AND TEST ZONES**

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
PARKMAN	4,056		<input type="checkbox"/>	<input type="checkbox"/>	
SUSSEX	4,480	4,788	<input type="checkbox"/>	<input type="checkbox"/>	
SHANNON	5,052	5,074	<input type="checkbox"/>	<input type="checkbox"/>	
NIOBRARA	7,446		<input type="checkbox"/>	<input type="checkbox"/>	
FORT HAYS	7,725		<input type="checkbox"/>	<input type="checkbox"/>	
CODELL	7,747		<input type="checkbox"/>	<input type="checkbox"/>	
J SAND	8,171		<input type="checkbox"/>	<input type="checkbox"/>	

## Comment:

Did not drill conductor hole on this well. Engineering felt there was not enough coal in area to set conductor casing.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_

Print Name: Cindy Vue

Title: Regulatory Analyst II

Date: \_\_\_\_\_

Email: Cindy.Vue@anadarko.com

Based on the information provided herein, this Drilling Completion Report (Form 5) complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

**Attachment Check List**

Att Doc Num	Name
400181967	DIRECTIONAL SURVEY
400181968	CEMENT JOB SUMMARY

Total Attach: 2 Files

**General Comments**

**User Group**      **Comment**      **Comment Date**

--	--	--

Total: 0 comment(s)