

FORM
2
Rev
12/05

State of Colorado
Oil and Gas Conservation Commission
1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400175127

Plugging Bond Surety

20100017

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☒

Refiling ☐
Sidetrack ☐

3. Name of Operator: ENCANA OIL & GAS (USA) INC 4. COGCC Operator Number: 100185

5. Address: 370 17TH ST STE 1700
City: DENVER State: CO Zip: 80202-5632

6. Contact Name: Heather Mitchell Phone: (720)876-3070 Fax: (720)876-4070
Email: heather.mitchell@encana.com

7. Well Name: Benzel Fee Well Number: 25-7E (F25NWB)

8. Unit Name (if appl): Grass Mesa Unit Unit Number: COC-056608X

9. Proposed Total Measured Depth: 9373

WELL LOCATION INFORMATION

10. QtrQtr: SENW Sec: 25 Twp: 6S Rng: 93W Meridian: 6
Latitude: 39.500141 Longitude: -107.725936

Footage at Surface: 1682 feet FNL/FSL FNL 2171 feet FEL/FWL FWL

11. Field Name: Mamm Creek Field Number: 52500

12. Ground Elevation: 5823 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 11/08/2010 PDOP Reading: 2.4 Instrument Operator's Name: C.D. Slaugh

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 1846 FNL 2603 FEL FEL Bottom Hole: FNL/FSL 1846 FNL 2603 FEL FEL
Sec: 25 Twp: 6S Rng: 93W Sec: 25 Twp: 6S Rng: 93W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 1894 ft

18. Distance to nearest property line: 502 ft 19. Distance to nearest well permitted/completed in the same formation: 200 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Illes	ILES			
Williams Fork	WMFK			

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No: ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
T6S-R93W - Sec. 23: NESE, Sec. 24: N2, NWSW, E2SE, Sec. 25: E2NE, SWNE

25. Distance to Nearest Mineral Lease Line: _____ 67 ft _____ 26. Total Acres in Lease: _____ 627 _____

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☐ Offsite ☒ Onsite **If 28, 29, or 30 are "Yes" a pit permit may be required.**

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	24	16	Linepipe	0	40	5	40	0
SURF	12+1/4	9+5/8	36	0	1,405	435	1,405	0
2ND	7+7/8	4+1/2	12	0	9,373	917	9,373	

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments # 17 is the distance to the nearest road. Production cement will run to 500' above TOG

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Heather Mitchell

Title: Regulatory Analyst Date: 6/14/2011 Email: heather.mitchell@encana.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 7/6/2011

API NUMBER

05 045 20842 00

Permit Number: _____ Expiration Date: 7/5/2013

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1.) THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1 MILE IS 500 FEET DEEP.

2.) PRODUCTION CASING CEMENT TOP VERIFICATION BY CBL REQUIRED.

Attachment Check List

Att Doc Num	Name
400175127	FORM 2 SUBMITTED
400175167	DEVIATED DRILLING PLAN
400175168	PLAT
400175237	SURFACE AGRMT/SURETY

Total Attach: 4 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	e-mailed operator to notify change of longitude to correct value for well location and also requested surface bond ID#	6/15/2011 8:19:02 AM

Total: 1 comment(s)

BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)