

FORM
2

Rev
12/05

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400180620

Plugging Bond Surety

20040060

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ☒ COMMINGLE ☒

Refiling ☐

Sidetrack ☐

3. Name of Operator: BARRETT CORPORATION* BILL

4. COGCC Operator Number: 10071

5. Address: 1099 18TH ST STE 2300

City: DENVER State: CO Zip: 80202

6. Contact Name: Mary Pobuda Phone: (303)312-8511 Fax: (303)291-0420

Email: mpobuda@billbarrettcorp.com

7. Well Name: EPPERLY Well Number: 24D-23-692

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 7906

WELL LOCATION INFORMATION

10. QtrQtr: NWSW Sec: 23 Twp: 6S Rng: 92W Meridian: 6

Latitude: 39.511770 Longitude: -107.640602

Footage at Surface: 2321 feet FNL/FSL 866 feet FEL/FWL FWL

11. Field Name: MAMM CREEK Field Number: 52500

12. Ground Elevation: 5859 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 08/13/2010 PDOP Reading: 6.0 Instrument Operator's Name: JAMES KALMON

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 1121 FSL 1994 FWL FWL Bottom Hole: FNL/FSL 1121 FSL 1994 FWL FWL
Sec: 23 Twp: 6S Rng: 92W Sec: 23 Twp: 6S Rng: 92W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 531 ft

18. Distance to nearest property line: 313 ft 19. Distance to nearest well permitted/completed in the same formation: 325 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
ILES	ILES	191-10	320	S/2
WILLIAMS FORK	WMFK	191-8	320	S/2

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: CO10235

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☒ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

See attached lease map

25. Distance to Nearest Mineral Lease Line: 1121 ft

26. Total Acres in Lease: 2125

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☐ Offsite ☒ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: EVAP & BURY

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	24	14	36	0	40		40	
SURF	12+1/4	9+5/8	36	0	758	240	758	
1ST	7+7/8	4+1/2	11.6	0	7,906	800	7,906	3,378

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Mary Pobuda

Title: Permit Analyst Date: 7/1/2011 Email: mpobuda@billbarrettcorp.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

API NUMBER

05

Permit Number: _____ Expiration Date: _____

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Attachment Check List

Att Doc Num	Name
400180620	FORM 2 SUBMITTED
400180625	WELL LOCATION PLAT
400180626	MULTI-WELL PLAN
400180627	DEVIATED DRILLING PLAN
400180628	LEASE MAP

Total Attach: 5 Files

General Comments

User Group	Comment	Comment Date

Total: 0 comment(s)

BMP

Type	Comment

Total: 0 comment(s)