

FORM  
2  
Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission  
1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400173450

Plugging Bond Surety

20010124

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_  
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☐

Refiling ☐  
Sidetrack ☐

3. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP 4. COGCC Operator Number: 47120  
5. Address: P O BOX 173779  
City: DENVER State: CO Zip: 80217-3779  
6. Contact Name: CHERYL LIGHT Phone: (720)929-6461 Fax: (720)929-7461  
Email: CHERYL.LIGHT@ANADARKO.COM  
7. Well Name: RIVERBEND Well Number: 31-18  
8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_  
9. Proposed Total Measured Depth: 8173

WELL LOCATION INFORMATION

10. QtrQtr: NENE Sec: 13 Twp: 1N Rng: 67W Meridian: 6  
Latitude: 40.056794 Longitude: -104.831596

Footage at Surface: 566 feet FNL/FSL FNL 519 feet FEL/FWL FEL

11. Field Name: WATTENBERG Field Number: 90750  
12. Ground Elevation: 4913 13. County: WELD

14. GPS Data:

Date of Measurement: 04/27/2010 PDOP Reading: 1.9 Instrument Operator's Name: CHRIS PEARSON

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 1320 FNL 50 FWL 1320 FNL 50 FWL  
Bottom Hole: FNL/FSL 1320 FNL 50 FWL  
Sec: 18 Twp: 1N Rng: 67W Sec: 18 Twp: 1N Rng: 67W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 1594 ft

18. Distance to nearest property line: 524 ft 19. Distance to nearest well permitted/completed in the same formation: 888 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
J SAND	JSND		160	GWA
NIOBRARA CODELL	NB-CD	407	160	GWA

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: \_\_\_\_\_

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No: ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
PLEASE SEE ATTACHED OIL AND GAS LEASE.

25. Distance to Nearest Mineral Lease Line: \_\_\_\_\_ 1320 ft 26. Total Acres in Lease: \_\_\_\_\_ 408

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: \_\_\_\_\_

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

If 28, 29, or 30 are "Yes" a pit permit may be required.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	8+5/8	24.0	0	900	630	900	0
1ST	7+7/8	4+1/2	11.6	0	8,173	200	8,173	

32. BOP Equipment Type: ☒ Annular Preventer ☐ Double Ram ☒ Rotating Head ☐ None

33. Comments NO CONDUCTOR CASING WILL BE USED. UNIT CONFIGURATION NIOBRARA-CODELL/JSAND 1N-67W-18: W/2NW4, 1N-67W-13: E/2NE/4

34. Location ID: \_\_\_\_\_ 331919

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: CHERYL LIGHT

Title: SR. REGULATORY ANALYST Date: 6/16/2011 Email: DJREGULATORY@ANADARK

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 7/8/2011

#### API NUMBER

05 123 33941 00

Permit Number: \_\_\_\_\_ Expiration Date: 7/7/2013

#### CONDITIONS OF APPROVAL, IF ANY:

**All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.**

- 1) Note surface casing setting depth change from 900' to 970'. Increase cement coverage accordingly and cement to surface.
- 2) Provide 24 hour notice of MIRU to Jim Precup at 303-469-1902 or e-mail at james.precup@state.co.us
- 3) Comply with Rule 317.i and provide cement coverage from TD to a minimum of 200' above Niobrara and from 200' below Sussex to 200' above Sussex. Verify coverage with cement bond log.
- 4) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

### **Attachment Check List**

Att Doc Num	Name
400173450	FORM 2 SUBMITTED
400173467	DEVIATED DRILLING PLAN
400173468	PLAT
400173470	TOPO MAP
400173471	30 DAY NOTICE LETTER
400173472	SURFACE AGRMT/SURETY
400173473	OIL & GAS LEASE
400173474	PROPOSED SPACING UNIT

Total Attach: 8 Files

### **General Comments**

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

### **BMP**

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)