

FORM
5A
Rev
02/08

State of Colorado
Oil and Gas Conservation Commission
1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:
400181350

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 10084
2. Name of Operator: PIONEER NATURAL RESOURCES USA INC
3. Address: 1401 17TH ST STE 1200
City: DENVER State: CO Zip: 80202
4. Contact Name: Judy Glinisty
Phone: (303) 675-2658
Fax: (303) 294-1275

5. API Number 05-071-08546-00
6. County: LAS ANIMAS
7. Well Name: GREY GOOSE
Well Number: 33-30
8. Location: QtrQtr: NWSE Section: 30 Township: 32S Range: 67W Meridian: 6
9. Field Name: PURGATOIRE RIVER Field Code: 70830

Completed Interval

FORMATION: RATON COAL Status: PRODUCING

Treatment Date: 05/25/2011 Date of First Production this formation: 06/13/2011
Perforations Top: 847 Bottom: 1747 No. Holes: 304 Hole size: 0.48

Provide a brief summary of the formation treatment: Open Hole:

To abandon three Raton intervals 1918' - 1921' , 1942' - 1945' and 2197' - 2200' via CIBP described below. Fraced new Raton intervals at 847' - 850' , 889' - 891' , 894' - 896' , 905' - 908' , 980' - 983' , 1150' - 1158' , 1208' - 1211' , 1256' - 1262' , 1290' - 1295' , 1327' - 1331' , 1396' - 1399' , 1422' - 1424' , 1430' - 1432' , 1520' - 1527' , 1589' - 1593' , 1607' - 1609' , 1626' - 1629' , 1668' - 1671' , 1707' - 1713' , 1720' - 1722' , 1744' - 1747'. 16/30 - 554,284# - N2 - 48,488 hscf - 2,905 bbls 15# linear - 126 gals 7.5% HCl.

This formation is commingled with another formation: Yes No

Test Information:

Date: 06/23/2011 Hours: 24 Bbls oil: 0 Mcf Gas: 31 Bbls H2O: 0
Calculated 24 hour rate: Bbls oil: 0 Mcf Gas: 31 Bbls H2O: 0 GOR: 0
Test Method: Pumping Casing PSI: 6 Tubing PSI: 0 Choke Size: 64/64
Gas Disposition: SOLD Gas Type: COAL GAS BTU Gas: 1004 API Gravity Oil: 0
Tubing Size: 2 + 7/8 Tubing Setting Depth: 1806 Tbg setting date: 06/20/2011 Packer Depth: 0

Reason for Non-Production:

Date formation Abandoned: 06/10/2011 Squeeze: Yes No If yes, number of sacks cmt _____
Bridge Plug Depth: 1870 Sacks cement on top: _____

FORMATION: VERMEJO COAL Status: ABANDONED COMPLETION

Treatment Date: _____ Date of First Production this formation: _____
Perforations Top: 2393 Bottom: 2686 No. Holes: 72 Hole size: _____

Provide a brief summary of the formation treatment: _____ Open Hole:

--- TO ABANDON VERMEJO FORMATION VIA CIBP DESCRIBED BELOW ---

This formation is commingled with another formation: Yes No

Test Information:

Date: _____ Hours: 0 Bbls oil: 0 Mcf Gas: 0 Bbls H2O: 0
Calculated 24 hour rate: Bbls oil: 0 Mcf Gas: 0 Bbls H2O: 0 GOR: 0
Test Method: 0 Casing PSI: 0 Tubing PSI: 0 Choke Size: 0
Gas Disposition: _____ Gas Type: _____ BTU Gas: 0 API Gravity Oil: 0
Tubing Size: 2 + 7/8 Tubing Setting Depth: 1806 Tbg setting date: 06/20/2011 Packer Depth: 0

Reason for Non-Production:

CIBP

Date formation Abandoned: 06/10/2011 Squeeze: Yes No If yes, number of sacks cmt _____

Bridge Plug Depth: 1870 Sacks cement on top: _____

Comment:

SUMMARY: Well was producing out of Raton/Vermejo with 1st production date of 12/18/2005. Well was then shut-in effective 5/1/2007 as no production for two years. After recompletion done on 5/25/2011 and setting of CIBP to abandon Vermejo, Raton formation started producing as of 6-13-2011.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Judy Glinisty

Title: Sr. Engineering Tech Date: 7/1/2011 Email Judy.Glinisty@pxd.com

Attachment Check List

Att Doc Num	Name
400181350	FORM 5A SUBMITTED
400181384	WELLBORE DIAGRAM

Total Attach: 2 Files

General Comments

User Group	Comment	Comment Date

Total: 0 comment(s)