

FORM
2

Rev
12/05

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400181674

Plugging Bond Surety

20100108

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER Pilot
SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refiling ☐

Sidetrack ☐

3. Name of Operator: CARRIZO OIL & GAS INC

4. COGCC Operator Number: 10338

5. Address: 1000 LOUISIANA STREET #1500

City: HOUSTON State: TX Zip: 77002

6. Contact Name: Terry Hoffman Phone: (720)542-8287 Fax: (720)542-9213

Email: terry@rockymountainpermitting.com

7. Well Name: Speaker Well Number: 1-27-31-8-61

8. Unit Name (if appl): Unit Number:

9. Proposed Total Measured Depth: 7040

WELL LOCATION INFORMATION

10. QtrQtr: NWNE Sec: 27 Twp: 8N Rng: 61W Meridian: 6

Latitude: 40.639280 Longitude: -104.188050

Footage at Surface: 292 feet FNL/FSL 1560 feet FEL/FWL FEL

11. Field Name: Wildcat Field Number: 99999

12. Ground Elevation: 4992 13. County: WELD

14. GPS Data:

Date of Measurement: 06/12/2011 PDOP Reading: 2.3 Instrument Operator's Name: Marc Woodard

15. If well is ☐ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL

Sec: Twp: Rng: Sec: Twp: Rng:

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 240 ft

18. Distance to nearest property line: 292 ft 19. Distance to nearest well permitted/completed in the same formation: 1201 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Niobrara	NBRR	535-13	640	All

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #:

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

T8N-R61W: Section 27: All; Section 28: E2; Section 35:N2NW4, SW4NW4 & NW4SW4

25. Distance to Nearest Mineral Lease Line: 292 ft

26. Total Acres in Lease: 1120

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☐ Offsite ☒ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Landfarm Burial or

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	9+5/8	36	0	1,400	534	1,400	0
OPEN HOLE	8+3/4			0	7,040	839	7,040	5,566

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments This well is for informational purposes only. This well will be plugged back after reaching TD (7040') with 839 sxs of cement. Top of cement will be 5566'. No conductor casing will be set. All footages 5280' are 1 mile or greater. This is a two-well pad; Speaker 2-27-31-8-61 is 2nd well on this pad.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Terry L. Hoffman

Title: Permit Agent Date: 7/8/2011 Email: terry@rockymountainpermitting.

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

API NUMBER

05

Permit Number: _____ Expiration Date: _____

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Attachment Check List

Att Doc Num	Name
400181674	FORM 2 SUBMITTED
400182297	PLAT
400184085	OIL & GAS LEASE

Total Attach: 3 Files

General Comments

User Group	Comment	Comment Date

Total: 0 comment(s)

BMP

Type	Comment
Construction	<p>Operator will ensure 110 percent secondary containment for any volume of fluids contained at the well site during drilling and completion.</p> <p>Operator will implement best management practices to contain any unintentional release of fluids.</p> <p>Operator has designed the well pad with insloping and a storm water control ditch to prevent storm water run-on/runoff and the release of fluids from the location. See attached Construction Layout Drawing.</p> <p>Fresh water for the Fresh Water Storage Pit comes from water provider; water sources permitted for consumable industrial use.</p> <p>Operator shall not allow any fluids to flow back to the Fresh Water Storage Pit.</p> <p>Fresh Water Storage Pit shall contain fresh water only and signage prohibiting the use of the pit for any fluid that does not come from municipal, irrigation or surface water source.</p> <p>The location will be fenced and the fenced area will include the Fresh Water Storage Pit.</p> <p>The COGCC to be notified 48 hours prior to construction of the Fresh Water Storage Pit.</p>

Total: 1 comment(s)