

FORM
5Rev
02/08State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400172545

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 47120

2. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP

3. Address: P O BOX 173779

City: DENVER State: CO Zip: 80217-

4. Contact Name: Cindy Vue

Phone: (720) 929-6832

Fax: (720) 929-7832

5. API Number 05-123-31291-00

6. County: WELD

7. Well Name: NRC

Well Number: 38-9

8. Location: QtrQtr: SWSE Section: 9 Township: 1N Range: 67W Meridian: 6

Footage at surface: Distance: 1071 feet Direction: FSL Distance: 1500 feet Direction: FEL

As Drilled Latitude: 40.061215 As Drilled Longitude: -104.891686

GPS Data:

Data of Measurement: 11/03/2010 PDOP Reading: 2.2 GPS Instrument Operator's Name: Renee Doiron

** If directional footage

at Top of Prod. Zone Distance: 66 feet Direction: FSL Distance: 80 feet Direction: FEL

Sec: 9 Twp: 1N Rng: 67W

at Bottom Hole Distance: 67 feet Direction: FSL Distance: 72 feet Direction: FEL

Sec: 9 Twp: 1N Rng: 67W

9. Field Name: SPINDLE

10. Field Number: 77900

11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 09/28/2010 13. Date TD: 10/04/2010 14. Date Casing Set or D&A: 10/05/2010

15. Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 8621 TVD 8238 17 Plug Back Total Depth MD 8581 TVD 8198

18. Elevations GR 5025 KB 5040

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

CD-CN-ML, DI-GL-GR; CBL-12/15/10; CBL 5/9/11

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
SURF	12+1/4	8+5/8	24#	0	1,016	680	0	1,016	CALC
1ST	7+7/8	4+1/2	11.6#	0	8,613	140	8,100	8,613	CBL

ADDITIONAL CEMENT

Cement work date:

Details of work:

DV TOOL SET 10/7/2010
 CMT SQUEEZE 1/24/2011 -120 SX CMT
 CMT SQUEEZE 5/03/2011 -30 SX CMT

Method used	String	Cementing tool setting/pref depth	Cement volume	Cement top	Cement bottom
DV TOOL	1ST	5,930	405	1,254	5,835
SQUEEZE	1ST	7,430	120	7,410	8,044
SQUEEZE	1ST	7,284	30	7,284	7,314

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
SUSSEX	4,696		<input type="checkbox"/>	<input type="checkbox"/>	
NIOBRARA	7,678		<input type="checkbox"/>	<input type="checkbox"/>	
FORT HAYS	8,000		<input type="checkbox"/>	<input type="checkbox"/>	
CODELL	8,021		<input type="checkbox"/>	<input type="checkbox"/>	
J SAND	8,465		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Cindy Vue

Title: Regulatory Analyst II Date: _____ Email: Cindy.Vue@anadarko.com

Based on the information provided herein, this Drilling Completion Report (Form 5) complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

Attachment Check List

Att Doc Num	Name
400172589	DIRECTIONAL SURVEY
400172590	CEMENT JOB SUMMARY
400172729	CEMENT JOB SUMMARY
400172731	CEMENT JOB SUMMARY

Total Attach: 4 Files

General Comments

User Group **Comment** **Comment Date**

--	--	--

Total: 0 comment(s)