


FORM 2 Rev 12/05	State of Colorado Oil and Gas Conservation Commission 1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109		<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 25%;">DE</td> <td style="width: 25%;">ET</td> <td style="width: 25%;">OE</td> <td style="width: 25%;">ES</td> </tr> </table>	DE	ET	OE	ES
DE	ET	OE	ES				
APPLICATION FOR PERMIT TO:			Document Number: 400175479 Plugging Bond Surety 20100108				
1. <input checked="" type="checkbox"/> Drill, <input type="checkbox"/> Deepen, <input type="checkbox"/> Re-enter, <input type="checkbox"/> Recomplete and Operate							
2. TYPE OF WELL OIL <input checked="" type="checkbox"/> GAS <input type="checkbox"/> COALBED <input type="checkbox"/> OTHER <input type="checkbox"/> Pilot _____ SINGLE ZONE <input checked="" type="checkbox"/> MULTIPLE ZONE <input type="checkbox"/> COMMINGLE ZONE <input type="checkbox"/>		Refiling <input type="checkbox"/> Sidetrack <input type="checkbox"/>					
3. Name of Operator: <u>CARRIZO OIL & GAS INC</u>		4. COGCC Operator Number: <u>10338</u>					
5. Address: <u>1000 LOUISIANA STREET #1500</u> City: <u>HOUSTON</u> State: <u>TX</u> Zip: <u>77002</u>							
6. Contact Name: <u>Terry Hoffman</u> Phone: <u>(720)542-8287</u> Fax: <u>(720)542-9213</u> Email: <u>terry@rockymountainpermitting.com</u>							
7. Well Name: <u>Ptasnik</u>		Well Number: <u>33-11-9-59</u>					
8. Unit Name (if appl): _____		Unit Number: _____					
9. Proposed Total Measured Depth: <u>6806</u>							
WELL LOCATION INFORMATION							
10. QtrQtr: <u>NWNW</u> Sec: <u>33</u> Twp: <u>9N</u> Rng: <u>59W</u> Meridian: <u>6</u> Latitude: <u>40.713375</u> Longitude: <u>-103.991514</u>							
Footage at Surface: <u>245</u> feet FNL/FSL <u>245</u> feet FEL/FWL <u>FWL</u>							
11. Field Name: <u>Wildcat</u>		Field Number: <u>99999</u>					
12. Ground Elevation: <u>4855</u>		13. County: <u>WELD</u>					
14. GPS Data: Date of Measurement: <u>05/27/2011</u> PDOP Reading: <u>2.1</u> Instrument Operator's Name: <u>L.S.</u>							
15. If well is <input type="checkbox"/> Directional <input type="checkbox"/> Horizontal (highly deviated) submit deviated drilling plan. Footage at Top of Prod Zone: FNL/FSL _____ FEL/FWL _____ Bottom Hole: FNL/FSL _____ FEL/FWL _____ Sec: _____ Twp: _____ Rng: _____ Sec: _____ Twp: _____ Rng: _____							
16. Is location in a high density area? (Rule 603b)? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No							
17. Distance to the nearest building, public road, above ground utility or railroad: <u>278</u> ft							
18. Distance to nearest property line: <u>245</u> ft 19. Distance to nearest well permitted/completed in the same formation: <u>953</u> ft							
20. LEASE, SPACING AND POOLING INFORMATION							
Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)			
Niobrara	NBRR	535-3	640	All			

IMPORTANT: SOME DATA FIELDS HAVE BEEN MODIFIED.

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: 20100170

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☒ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
See attached full lease description, to large to type.

25. Distance to Nearest Mineral Lease Line: 245 ft 26. Total Acres in Lease: 6630

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Landfarm Burial or Evaporati

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	9+5/8	36	0	1,400	534	1,400	0
OPEN HOLE	8+3/4			0	6,806	851	6,806	5,312

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments This well is for informational purposes only. This well will be plugged back after reaching TD (6806') with 851 sxs of cement. Top of cement will be 5312'. No conductor casing will be set. All footages 5280' are 1 mile or greater.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Terry L. Hoffman

Title: Permit Agent Date: 6/16/2011 Email: terry@rockymountainpermitting.

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 7/14/2011

API NUMBER

05 123 33945 00

Permit Number: _____ Expiration Date: 7/13/2013

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

A well being completed deeper than 2500 feet must be 600 feet from a lease line or requires an approved exception location. per rule 318a..

- 1) Provide 24 hour notice of MIRU to Colby Horton at 970-467-2517 or e-mail at colby.horton@state.co.us.
- 2) Plug back pilot hole as proposed on line 33 comments or at a minimum: Set 70 sks cement from 50' below D-Sand base to 100' above D-Sand top. Set 40 sks cement 50' above Niobrara top. This is in addition to kick off plug.

Attachment Check List

Att Doc Num	Name
400175479	FORM 2 SUBMITTED
400175527	PLAT
400176132	LEGAL/LEASE DESCRIPTION

Total Attach: 3 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	This is a pilot/lateral drilling plan. The permits will be on hold pending the completion of the 20 day public comment period at which time they will be approved together to maintain proper API number designations.	6/17/2011 1:01:50 PM

Total: 1 comment(s)

BMP

<u>Type</u>	<u>Comment</u>
Construction	Operator will ensure 110 percent secondary containment for any volume of fluids contained at the well site during drilling and completion. Operator will implement best management practices to contain any unintentional release of fluids. Operator has designed the well pad with insloping and a storm water control ditch to prevent storm water run-on/runoff and the release of fluids from the location. See attached Construction Layout Drawing. Fresh water for the Fresh Water Storage Pit comes from water provider; water sources permitted for consumable industrial use. Operator shall not allow any fluids to flow back to the Fresh Water Storage Pit. Fresh Water Storage Pit shall contain fresh water only and signage prohibiting the use of the pit for any fluid that does not come from municipal, irrigation or surface water source. The location will be fenced and the fenced area will include the Fresh Water Storage Pit. The COGCC to be notified 48 hours prior to construction of the Fresh Water Storage Pit.

Total: 1 comment(s)