

FORM
2

Rev
12/05

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400181747

Plugging Bond Surety

20090069

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ☒ COMMINGLE ☐

Refiling ☒

Sidetrack ☐

3. Name of Operator: DELTA PETROLEUM CORPORATION

4. COGCC Operator Number: 16800

5. Address: 370 17TH ST STE 4300

City: DENVER State: CO Zip: 80202

6. Contact Name: Jennifer Barnett Phone: (303)578-2536 Fax: ()

Email: jbarnett@progressivepcs.net

7. Well Name: NVega Well Number: 22-222

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 8679

WELL LOCATION INFORMATION

10. QtrQtr: NESW Sec: 22 Twp: 9S Rng: 93W Meridian: 6

Latitude: 39.260814 Longitude: -107.757917

Footage at Surface: 2057 feet FNL/FSL FSL 2074 feet FEL/FWL FWL

11. Field Name: Buzzard Creek Field Number: 9500

12. Ground Elevation: 7493 13. County: MESA

14. GPS Data:

Date of Measurement: 08/27/2007 PDOP Reading: 2.3 Instrument Operator's Name: Bart Hunting, Uintah Surveying

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 1500 FNL 1740 FWL FWL Bottom Hole: FNL/FSL 1500 FNL 1740 FWL FWL
Sec: 22 Twp: 9S Rng: 93W Sec: 22 Twp: 9S Rng: 93W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 4350 ft

18. Distance to nearest property line: 560 ft 19. Distance to nearest well permitted/completed in the same formation: 650 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
MESAVERDE	MVRD	369-4		

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

Please see attached.

25. Distance to Nearest Mineral Lease Line: 192 ft

26. Total Acres in Lease: 1749

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☐ Offsite ☒ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Closed Loop

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	24	16	55	0	60	200	60	0
SURF	12+1/4	8+5/8	24, 32	0	2,200	740	2,200	0
1ST	7+7/8	4+1/2	11.6	0	8,679	477	8,679	5,415

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments I certify that all conditions in the original permit are the same. There have been no changes to land use, well construction or the lease. This pad is built. No expansion or additional disturbance will occur. Closed loop system will be used. DELTA PETROLEUM CORP IS THE SURFACE OWNER. There will not be a 30 day letter or SUA attached. This Refile Form 2 does not require a Form 2A because the pad has been constructed, a closed loop system is being used so no pits need to be constructed, the refiled well will not require any expansion/additional surface disturbance of the pad. The location is not in a wildlife restricted surface occupancy area (RSO); consultation with CDOW is not required and the location does not require a variance from any of the rules listed in 306.d.(1).(A).(ii).; consultation with CDPHE is not required.

34. Location ID: 334465

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☐ Yes ☒ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Jennifer Barnett

Title: Regulatory Agent

Date: _____

Email: jbarnett@progressivepcs.net

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

API NUMBER

05 077 09919 00

Permit Number: _____ Expiration Date: _____

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Attachment Check List

Att Doc Num	Name
400184175	LEGAL/LEASE DESCRIPTION

Total Attach: 1 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)