


<b>FORM</b> <b>2</b> Rev 12/05	<b>State of Colorado</b> <b>Oil and Gas Conservation Commission</b> 1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109		<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 25%;">DE</td> <td style="width: 25%;">ET</td> <td style="width: 25%;">OE</td> <td style="width: 25%;">ES</td> </tr> </table>	DE	ET	OE	ES
DE	ET	OE	ES				
<b>APPLICATION FOR PERMIT TO:</b>			Document Number:  400175290  Plugging Bond Surety  19880020				
1. <input checked="" type="checkbox"/> <b>Drill,</b> <input type="checkbox"/> Deepen, <input type="checkbox"/> Re-enter, <input type="checkbox"/> Recomplete and Operate							
2. TYPE OF WELL OIL <input type="checkbox"/> GAS <input checked="" type="checkbox"/> COALBED <input type="checkbox"/> OTHER _____ SINGLE ZONE <input checked="" type="checkbox"/> MULTIPLE ZONE <input type="checkbox"/> COMMINGLE ZONE <input type="checkbox"/>		Refiling <input checked="" type="checkbox"/> Sidetrack <input type="checkbox"/>					
3. Name of Operator: <u>MARATHON OIL COMPANY</u>		4. COGCC Operator Number: <u>53650</u>					
5. Address: <u>5555 SAN FELIPE</u> City: <u>HOUSTON</u> State: <u>TX</u> Zip: <u>77056</u>							
6. Contact Name: <u>Anna Walls</u> Phone: <u>(713)296-3468</u> Fax: <u>(713)513-4394</u> Email: <u>avwalls@marathonoil.com</u>							
7. Well Name: <u>596-30C</u>		Well Number: <u>26</u>					
8. Unit Name (if appl): _____		Unit Number: _____					
9. Proposed Total Measured Depth: <u>9942</u>							
<b>WELL LOCATION INFORMATION</b>							
10. QtrQtr: <u>Lot 3</u> Sec: <u>30</u> Twp: <u>5S</u> Rng: <u>96W</u> Meridian: <u>6</u> Latitude: <u>39.585430</u> Longitude: <u>-108.213330</u>							
Footage at Surface: <u>2387</u> feet    FNL/FSL <u>FSL</u> <u>1151</u> feet    FEL/FWL <u>FWL</u>							
11. Field Name: <u>Trail Ridge</u>		Field Number: <u>83825</u>					
12. Ground Elevation: <u>8195</u>		13. County: <u>GARFIELD</u>					
14. GPS Data: Date of Measurement: <u>07/22/2008</u> PDOP Reading: <u>2.2</u> Instrument Operator's Name: <u>William H Dolinar</u>							
15. If well is <input checked="" type="checkbox"/> Directional <input type="checkbox"/> Horizontal (highly deviated) <b>submit deviated drilling plan.</b> Footage at Top of Prod Zone:    FNL/FSL    FEL/FWL    Bottom Hole:    FNL/FSL    FEL/FWL <u>841</u> <u>FSL</u> <u>987</u> <u>FWL</u> <u>841</u> <u>FSL</u> <u>987</u> <u>FWL</u> Sec: <u>30</u> Twp: <u>5S</u> Rng: <u>96W</u> Sec: <u>30</u> Twp: <u>5S</u> Rng: <u>96W</u>							
16. Is location in a high density area? (Rule 603b)? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No							
17. Distance to the nearest building, public road, above ground utility or railroad: <u>4 mi</u>							
18. Distance to nearest property line: <u>1151 ft</u> 19. Distance to nearest well permitted/completed in the same formation: <u>640 ft</u>							
<b>20. LEASE, SPACING AND POOLING INFORMATION</b>							
Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)			
Williams Fork	WMFK	510-18	320	S/2			

**IMPORTANT: SOME DATA FIELDS HAVE BEEN MODIFIED.**

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: \_\_\_\_\_

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
see attached - purple

25. Distance to Nearest Mineral Lease Line: \_\_\_\_\_ 987 ft \_\_\_\_\_ 26. Total Acres in Lease: \_\_\_\_\_ 4541 \_\_\_\_\_

**DRILLING PLANS AND PROCEDURES**

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: evaporation/backfill

If 28, 29, or 30 are "Yes" a pit permit may be required.

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	20	16		0	140		140	0
SURF	14+3/4	9+5/8	36	0	2,000	1,000	2,000	0
1ST	8+3/4	4+1/2	11.6	0	9,942	675	9,942	5,500

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments Surface owned by: Chevron Minerals owned by: Chevron There are no visible improvements within 400' of wellhead. Well pad has not been built. Not in a wildlife RSO. Change surface casing setting depth to 2000'.

34. Location ID: \_\_\_\_\_ 336010 \_\_\_\_\_

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Anna Walls

Title: Regulatory Compliance Rep Date: 6/16/2011 Email: avwalls@marathonoil.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 7/14/2011

**API NUMBER**

05 045 18161 00

Permit Number: \_\_\_\_\_ Expiration Date: 7/13/2013

**CONDITIONS OF APPROVAL, IF ANY:**

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

(1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.

(2) GARFIELD COUNTY RULISON-FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE.

(3) THE MOISTURE CONTENT OF ANY DRILL CUTTINGS IN A CUTTINGS PIT, TRENCH, OR PILE SHALL BE AS LOW AS PRACTICABLE TO PREVENT ACCUMULATION OF LIQUIDS GREATER THAN DE-MINIMIS AMOUNTS. AT THE TIME OF CLOSURE, THE DRILL CUTTINGS MUST ALSO MEET THE APPLICABLE STANDARDS OF TABLE 910-1.

(4) NO PORTION OF ANY PIT THAT WILL BE USED TO HOLD LIQUIDS SHALL BE CONSTRUCTED ON FILL MATERIAL, UNLESS THE PIT AND FILL SLOPE ARE DESIGNED AND CERTIFIED BY A PROFESSIONAL ENGINEER, SUBJECT TO REVIEW AND APPROVAL BY THE DIRECTOR PRIOR TO CONSTRUCTION OF THE PIT. THE CONSTRUCTION AND LINING OF THE PIT SHALL BE SUPERVISED BY A PROFESSIONAL ENGINEER OR THEIR AGENT. THE ENTIRE BASE OF THE PIT MUST BE IN CUT.

(5) THE SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1-MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1-MILE IS 00 FEET DEEP.

### **Attachment Check List**

Att Doc Num	Name
400175290	FORM 2 SUBMITTED
400175292	30 DAY NOTICE LETTER

Total Attach: 2 Files

### **General Comments**

<b><u>User Group</u></b>	<b><u>Comment</u></b>	<b><u>Comment Date</u></b>
Permit	Changed SHL to match original filing; bhl was erroneously reported as shl Checked box to indicate well will be directional Refilled well will not require any expansion/additional surface disturbance of the pad. Statement removed per Anna Walls.	6/22/2011 11:24:18 AM

Total: 1 comment(s)

### **BMP**

<b><u>Type</u></b>	<b><u>Comment</u></b>
Wildlife	see approved Wildlife Mitigation Plan

Total: 1 comment(s)