


<b>FORM</b> <b>2</b> Rev 12/05	<b>State of Colorado</b> <b>Oil and Gas Conservation Commission</b> 1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109		<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 25%;">DE</td> <td style="width: 25%;">ET</td> <td style="width: 25%;">OE</td> <td style="width: 25%;">ES</td> </tr> </table> Document Number: 400170978  Plugging Bond Surety 20100108	DE	ET	OE	ES
DE	ET	OE	ES				
<b>APPLICATION FOR PERMIT TO:</b>							
1. <input checked="" type="checkbox"/> <b>Drill,</b> <input type="checkbox"/> Deepen, <input type="checkbox"/> Re-enter, <input type="checkbox"/> Recomplete and Operate							
2. TYPE OF WELL OIL <input checked="" type="checkbox"/> GAS <input type="checkbox"/> COALBED <input type="checkbox"/> OTHER <input type="checkbox"/> <u>HORIZONTAL</u> SINGLE ZONE <input type="checkbox"/> MULTIPLE ZONE <input type="checkbox"/> COMMINGLE ZONE <input type="checkbox"/>		Refiling <input type="checkbox"/> Sidetrack <input checked="" type="checkbox"/>					
3. Name of Operator: <u>CARRIZO OIL &amp; GAS INC</u>		4. COGCC Operator Number: <u>10338</u>					
5. Address: <u>1000 LOUISIANA STREET #1500</u> City: <u>HOUSTON</u> State: <u>TX</u> Zip: <u>77002</u>							
6. Contact Name: <u>Fabrianna Venaducci</u> Phone: <u>(303)279-0789</u> Fax: <u>(303)279-1124</u> Email: <u>fabrianna@jameskaro.com</u>							
7. Well Name: <u>Pergamos</u>		Well Number: <u>3-44-7-60</u>					
8. Unit Name (if appl): _____		Unit Number: _____					
9. Proposed Total Measured Depth: <u>12181</u>							
<b>WELL LOCATION INFORMATION</b>							
10. QtrQtr: <u>SESE</u> Sec: <u>3</u> Twp: <u>7N</u> Rng: <u>60W</u> Meridian: <u>6</u> Latitude: <u>40.597800</u> Longitude: <u>-104.070200</u>							
Footage at Surface: <u>297</u> feet      FNL/FSL <u>FSL</u> FEL/FWL <u>FEL</u>							
11. Field Name: <u>wildcat</u>		Field Number: <u>99999</u>					
12. Ground Elevation: <u>4935.5</u>		13. County: <u>WELD</u>					
14. GPS Data: Date of Measurement: <u>04/12/2011</u> PDOP Reading: <u>1.5</u> Instrument Operator's Name: <u>George Allen</u>							
15. If well is <input type="checkbox"/> Directional <input checked="" type="checkbox"/> Horizontal (highly deviated) <b>submit deviated drilling plan.</b> Footage at Top of Prod Zone:      FNL/FSL      FEL/FWL      Bottom Hole:      FNL/FSL      FEL/FWL <u>705</u> <u>FSL</u> <u>705</u> <u>FEL</u> <u>650</u> <u>FNL</u> <u>650</u> <u>FWL</u> Sec: <u>3</u> Twp: <u>7N</u> Rng: <u>60W</u> Sec: <u>3</u> Twp: <u>7N</u> Rng: <u>60W</u>							
16. Is location in a high density area? (Rule 603b)? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No							
17. Distance to the nearest building, public road, above ground utility or railroad: <u>240</u>							
18. Distance to nearest property line: <u>297 ft</u> 19. Distance to nearest well permitted/completed in the same formation: <u>5280 ft</u>							
<b>20. LEASE, SPACING AND POOLING INFORMATION</b>							
Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)			
Niobrara	NBRR	535-41	640	ALL			

**IMPORTANT: SOME DATA FIELDS HAVE BEEN MODIFIED.**

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: 20100170

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☒ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
7N, 60W, Sec 3: ALL; Sec 4: E2

25. Distance to Nearest Mineral Lease Line: 650 ft 26. Total Acres in Lease: 960

**DRILLING PLANS AND PROCEDURES**

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☐ Offsite ☒ Onsite **If 28, 29, or 30 are "Yes" a pit permit may be required.**

Method: ☒ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: \_\_\_\_\_

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
1ST	8+3/4	7	23	0	6,642	632	6,642	1,400
2ND	6+1/8	4+1/2	11.6	0	12,181	458	12,181	5,642

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments THIS FORM 2 IS SUBMITTED IN CONJUNCTION WITH FORM 2 (PILOT - DOCUMENT NUMBER 400170952) AND FORM 2A (DOCUMENT NUMBER 400171132). Application for a drilling and spacing unit has been made and is on the June 27 and 28, 2011 docket for approval. The nearest well permitted/completed in the same formation is more than 5280' from the bottom hole location.

34. Location ID: 424238

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Fabrianna Venaducci

Title: Contract Landman Date: 6/22/2011 Email: fabrianna@jameskaro.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 7/14/2011

**API NUMBER**

05 123 33955 01

Permit Number: \_\_\_\_\_ Expiration Date: 7/13/2013

**CONDITIONS OF APPROVAL, IF ANY:**

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- 1) Provide 24 hour notice of MIRU to Colby Horton at 970-467-2517 or e-mail at colby.horton@state.co.us.
- 2) Provide cement coverage from TD to a minimum of 200' above Niobrara. Verify coverage with cement bond log.
- 3) Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

### **Attachment Check List**

Att Doc Num	Name
400170978	FORM 2 SUBMITTED
400171648	WELL LOCATION PLAT
400173523	DEVIATED DRILLING PLAN

Total Attach: 3 Files

### **General Comments**

<b><u>User Group</u></b>	<b><u>Comment</u></b>	<b><u>Comment Date</u></b>
Permit	This is a pilot/lateral drilling plan. The permits will be on hold pending the completion of the 20 day public comment period at which time they will be approved together to maintain proper API number designations.	6/23/2011 1:45:11 PM

Total: 1 comment(s)

### **BMP**

<b><u>Type</u></b>	<b><u>Comment</u></b>
Drilling/Completion Operations	<p>Operator will ensure 110 percent secondary containment for any volume of fluids contained at the well site during drilling and completion. Operator will implement best management practices to contain any unintentional release of fluids.</p> <p>Fresh water for the Fresh Water Storage Pit comes from water provider; water sources permitted for consumable industrial use.</p> <p>Operator shall not allow any fluids to flow back to the Fresh Water Storage Pit.</p> <p>Fresh Water Storage Pit shall contain fresh water only and signage prohibiting the use of the pit for any fluid that does not come from municipal, irrigation or surface water source.</p>
Construction	<p>Operator has designed the well pad with insloping and a storm water control ditch to prevent storm water run-on/runoff and the release of fluids from the location. See attached Construction Layout Drawing.</p> <p>The location will be fenced and the fenced area will include the Fresh Water Storage Pit.</p> <p>The COGCC to be notified 48 hours prior to construction of the Fresh Water Storage Pit.</p>

Total: 2 comment(s)